

# City of Hagerstown



## NPDES PHASE II ANNUAL REPORT

June 2016 – July 2017



Prepared by:

City of Hagerstown  
Department of Parks & Engineering  
City Hall, Room 301  
1 E. Franklin Street  
Hagerstown, MD 21740

## **Introduction**

As required by the National Pollutant Discharge Elimination System (NPDES) Phase II program, the City of Hagerstown has prepared this report to document the City's progress in implementing the six minimum control measures required by the NPDES General Permit. The six measures include:

- Public Education
- Public Involvement
- Illicit Discharge Detection and Elimination
- Construction Site Runoff Control
- Post-Construction Runoff Control
- Pollution Prevention/Good Housekeeping

The City continues to work on attaining these goals, and making progress in each target area. The following sections of the report document the status of the City's efforts, and lay out our plan for attaining our goals over the next year.

A draft version of the new NPDES Phase II permit has been published, and indications are that the new permit will become effective in early 2018. It is believed that the new permit will require the City to provide water quality management for impervious surfaces that do not currently have management. Once the permit is issued, the City will review the new requirements and determine what steps need to be taken to be in compliance. The City is already taking steps to prepare for these anticipated requirements.

## **Public Education**

As with many municipal government efforts, the success of the City's NPDES Stormwater Pollution Prevention Program depends upon the cooperation of our City residents. Educating and involving residents in the program is a key step in reducing stormwater pollution.

With the implementation of the "Environmental Site Design" (ESD) stormwater regulations, the public was made aware of the need to reduce pollutants during multiple City council meetings, and meetings with the Washington County Builders Association. There has also been continued public discussion of the Watershed Implementation Plan (WIP) process, and the efforts to meet the Chesapeake Bay TMDL goals; the Washington County "WIP Team" meetings are open to the public, and representatives from most of the small municipalities attend the meetings so that they can pass pertinent information on to their residents. With ESD's emphasis on small-scale treatment facilities (e.g. rain gardens, landscape infiltration, rain barrels, etc.) instead of larger, "regional" solutions, the new regulations have helped to focus residents on things that they can do on their own to reduce stormwater pollution.

Recently, the City Council has authorized the solicitation of consultants to develop a stormwater utility, which would help the City to finance continued maintenance of the existing storm drainage/stormwater management system, and to construct new treatment facilities to meet the anticipated permit requirements. Through coverage of these Council discussions in the local media, the awareness of the general public on stormwater management issues has been raised.

One of the City's most successful ways to disseminate information to the general public is through the use of TV Channel 25, the City Government Channel. This Channel, a cooperative effort between the City and Antietam Cable Television, provides an effective means for the City to communicate information to the general viewing public (both City and Washington County residents). City Council meetings are televised live on Channel 25, as are press conferences and announcements of important events. The City's Public Information Office also produces video programs detailing City initiatives, upcoming City events, and other subjects. When live-action video programs are not running, a series of informative slides runs on Channel 25.

Another source of information on City programs is the City's internet web page ([www.hagerstownmd.org](http://www.hagerstownmd.org)). Under the "Engineering Department" section, visitors can find information on the City's Stormwater Management Program, and the requirements of the NPDES permit. There is also a "Homeowner Participation" page that list methods and techniques that private property owners to implement to help the City meet its NPDES goals. These techniques include rain gardens, rainwater harvesting, tree planting, lawn and garden maintenance, and other topics. The page also provides links to the webpages of other groups and agencies that have information on low impact design and environmental site design; those groups include the Alliance for the Chesapeake Bay, the Chesapeake Bay Foundation, the Chesapeake Bay Trust, the Center for Watershed Protection, and others. A screen shot of the Homeowner Participation page is shown below.

Home > Government > Departments > Engineering > Drainage & Stormwater Management > Homeowner Participation

Floodplains

NPDES Program

Stormwater Management Program

Homeowner Participation

Hamilton Run Action Plan

## Homeowner Participation

Homeowners and residents may ask "What can I do to decrease stormwater pollution?"

Reducing stormwater pollution isn't just a job for commercial and residential developers – it is an effort in which all property owners can participate. Here are some practices and techniques that you can use to decrease the volume of runoff entering our streams, or help to remove pollutants from that runoff.

### Disconnect your downspout

If the downspout from your house's rain gutter system empties directly onto a paved driveway or sidewalk, virtually all of that water (and the dirt, oil, trash, etc. that it picks up along the way) will end up in the City's storm drainage system and the waterways downstream. By redirecting the downspout to empty onto a lawn area or a landscaping bed, the runoff will be given an opportunity to infiltrate into the soil. Click on the photo below to link to tips on downspout disconnection from the [Alliance for the Chesapeake Bay](#).



### Harvest your rainwater

Another way to reduce the runoff from your property is to collect and store the water from your roof gutter system. By catching this water in a rain barrel or cistern, you will not only decrease the volume of runoff that leaves your property, you will have a source of "free" water that can be used for watering or irrigating your gardens and landscaping. Click on the photo below to link to information on the installation and use of rain barrels from the [Chesapeake Ecology Center](#).



“Homeowner Participation” page on the City’s website

The new webpage format has allowed the City to take advantage of social media outlets to disseminate information to the public. The City has a YouTube channel where video presentations on current topics are hosted, and also maintains a Facebook page that is used to alert and educate followers about City policies and programs.

Another method of public education is to provide stormwater-related information in “high traffic” areas, or in areas where the setting matches the context of the information being presented. The City has installed interpretive signs at several locations to highlight stormwater management/stream restoration projects, and to provide information on the Antietam Creek watershed. These types of signs are often a requirement of the State and Federal agencies that help to fund improvement projects.



Bio-retention facility along multi-use trail at Memorial Blvd.



Valley Road stream restoration site adjacent to Fairgrounds Park



Kiwanis Park canoe/kayak launch



Kiwanis Park Butterfly Waystation

The City has accepted an invitation to participate in the Washington County's STEM (science, technology, engineering, and mathematics) event in November 2017. The City plans to display information on the City's stormwater management program, and to distribute pamphlets on steps that homeowners can take to decrease stormwater pollution. One display board, showing the effect that stormwater pollution can have on aquatic plants and animals, has already been developed:

## Stormwater pollution threatens some of Maryland's iconic animals & foods

### The City of Hagerstown needs your help to protect our waterways and food supply

**All of the runoff from the lands of Washington County ends up in the Potomac River and (eventually) the Chesapeake Bay. Unfortunately, this runoff picks up pollutants along the way:**

**The Bay receives runoff from several major tributaries, including the Susquehanna, Potomac, Rappahannock, York, and James Rivers.**

Satellite Images of the Bay before and after 1.2 inches of rain on May 11 - 13

**Nutrients**

Animal and pet waste, along with the overuse of fertilizers, adds excess nitrogen and phosphorus to runoff, leading to algae blooms and low dissolved oxygen levels. Algae mats also block sunlight from reaching underwater grasses, causing them to die.

May 9                      May 15

**Sediment**

Sediment washed from construction sites and agricultural fields enters ditches and storm drainage systems, which convey it to our streams and rivers. Sediment also blocks sunlight, decreases underwater visibility, clogs channels, and buries oyster reefs.

### What is threatened?

<p><b>Underwater grasses</b></p> <ul style="list-style-type: none"> <li>Food source for waterfowl</li> <li>Shelter for young fish &amp; fish</li> </ul>	<p><b>Oysters</b></p> <ul style="list-style-type: none"> <li>Filter pollutants out of water</li> <li>Impacted by sediment &amp; bacteria</li> </ul>	<p><b>Blue crabs</b></p> <ul style="list-style-type: none"> <li>Rely on underwater grass habitat</li> <li>Endangered by low oxygen levels</li> </ul>	<p><b>Menhaden</b></p> <ul style="list-style-type: none"> <li>Foundation of Bay food chain</li> <li>Key ingredient in sq. fertilizers</li> </ul>	<p><b>Striped bass &amp; Smallmouth bass</b></p> <ul style="list-style-type: none"> <li>Impacted by low oxygen "dead zones" caused by algae blooms</li> <li>Poor water quality &amp; high temperatures make them susceptible to disease</li> </ul>	<p><b>Waterfowl</b></p> <ul style="list-style-type: none"> <li>Rely on aquatic vegetation for food</li> <li>Ingest pollutants in water and plants</li> </ul>
---	---	--	--	--	--

### What can you do?

**Manage lawn / pet waste / runoff**

- Mow lawn at a lower height
- Scrape leaves
- Use a rain garden
- Use a water filter

**Minimize erosion & water usage**

- Plant on slopes and soil
- Plant in areas in less open
- Use green practices to check

For more information on the City's Stormwater Management Program, visit [www.hagerstown.org/244/DireHageStormwaterManagement](http://www.hagerstown.org/244/DireHageStormwaterManagement)

Department of Parks and Engineering

The City also holds an annual Earth Day event at University Plaza in downtown Hagerstown. Focused on elementary school students, it gives the City an opportunity to make them aware of environmental issues, and present ideas of how they can help to preserve and improve the world that they live in. Below are photos from the 2017 event.





Pangborn Elementary students learning about recycling and trash collection




— HELP KEEP EARTH THE —  
**MOST BEAUTIFUL  
PLANET**

**RECYCLE RIGHT.**

Keep full water bottles and food items out of your recycle bin.  
And remember to recycle plastic bags at your participating retailer, not at home.



**City of Hagerstown  
EARTH DAY  
CELEBRATION**



## WELCOME

### 1. Welcome and Introductions

- Shannon Ryan, WHAG

### 2. Pledge of Allegiance

- Led by Mayor Robert E. Bruchey, II

### 3. Proclamation/ Remarks

- Mayor Robert E. Bruchey, II

### 4. Student Poetry - Students from Barbara Ingram School for the Arts

- Claire Dever, 9th grade
- Amelia Lowry, 11th grade
- Maddie Lynn, 11th grade

### 5. Remarks

- Rodney Tissue, City Engineer
- Robert Kong, Waste Management

### 6. Waste Management Recycling Game & Truck Visit

- Pangborn Elementary students will play a game to test their knowledge about recycling and will then have an up close look at a Waste Management recycling truck.

### 7. Program Concludes

- Shannon Ryan, WHAG



## PANGBORN ELEMENTARY STUDENTS

### Pangborn Elementary School Students

Teon Cain  
Emma Randolph  
Sha' Brea Bey  
Isabella Crockett  
Ava Myers  
Shaun Thomas  
Mason Hughes  
McKenzie Roseby  
Kennedi Branch  
Sam Peters  
Timothy Rinehart  
Michael Jimenez  
Gaitan  
Harmony Redding  
Juliana Nigh

Jayda Shewbridge  
Je'Diyah Wilkins  
Addison de la Rosa  
Brooklyn Rios  
Violette McDonald  
Lalayla Trost  
Brandon Monroe  
Erick Rivera  
Joey Dorsey  
Cheyenne Elliott  
Kimora Fruit  
Josiah Delrosario  
Hannah Worgul  
Jesse Eppard  
Keyani Saunders

### Special Thanks to:

Raegon Clutz, Coordinator Pangborn Elementary  
Teachers & Faculty at Pangborn Elementary School


*April 18, 2017*



## Public Involvement

The second component of the Stormwater Pollution Prevention Program is to actively involve the public in hands-on projects that address the program's goals. By involving the public, the City is able to foster the idea that all residents are stakeholders in the prevention of pollution, and the protection of our natural resources.

The City's single-stream recycling program continues to be a tremendous success. As the chart below indicates, the average monthly tonnage of materials collected since inception of the new program has pretty consistently exceeded 200 tons, which is more than twice the recycling rate that the City saw before the inception of the recycling collection program in 2012.



Unfortunately, the City has been informed by its waste collection contractor that, as of January 1, 2018, glass will no longer be collected for recycling due to low demand for glass cullet. This means that residents will be forced to dispose of their glass containers with their regular trash; not only will this result in material that was previously recycled ending up in the landfill, but it will also increase the tonnage (and cost) to provide refuse service to our residents.

On November 19, 2016, the City hosted an Electronics Recycling event. Partnering with Waste Management and Novotec Recycling, the City set up a collection area at Municipal Stadium. City residents were encouraged to bring their used computers, monitors, televisions, and other electric equipment for proper, free disposal, saving valuable landfill space and preventing potentially hazardous materials from entering our waterways. Over 24,000 pounds of electronic materials were collected at the event. Another Electronics Recycling event is scheduled for November 2017.

The City continues to sponsor a Bulk Trash pickup program. This program allows residents to call our Public Works department and schedule a pickup of large items (e.g. appliances, furniture, oversized trash items, etc.). While the City does charge a fee for this service, this call-based system has been found to work better than previous "Bulk Trash Pickup Week" programs when whole neighborhoods would set out bulky items for collection; trash and bulk items do not sit on sidewalks for days at a time, waiting for pickup. The City intends to continue this program indefinitely.

An increasing problem in the nation's waterways are the residual levels of prescription drugs and medications. When these materials are disposed of improperly, they can enter our streams through wastewater treatment plant effluent discharges and runoff collected by storm sewer systems. The Hagerstown Police Department has installed a "Medication Drop-off Box" in the lobby of the Police station; residents are encouraged to deposit unneeded or expired medications in the box – no questions asked. By providing a safe mechanism to dispose of medications, the chance that they will have a negative impact on our waterways is reduced. The Washington County Sherriff's office has a similar drop-off box at their central detention facility.



The City's Community Garden established in 2015, has continued to thrive. This facility, adjacent to Bester Elementary School, contains twenty-six garden beds that residents are able to rent during the growing season. The garden includes rain barrels and composting facilities to both support the planting beds, and to serve as an example of "best practices" to the public. A Gardener's Association was formed to manage the operation of the facility. Composting facilities have been incorporated into the design of the garden, and several of the beds were designed to meet the accessibility requirements of the Americans with Disabilities Act. The Association holds monthly meetings, and hosts seminars on a variety of gardening and renewable resource topics. Students from the adjacent Bester Elementary School visit the garden as part of their class curriculum.





The City has remained active in planting Street Trees in all the neighborhoods around the City. Much of the funding for this program has come via grants from the Department of Natural Resources and the Chesapeake Bay Trust. The City identifies neighborhoods and streets that have poor tree canopy coverage, and then analyzes each street to identify potential locations for the installation of new trees. The City has also worked with the local Neighborhoods 1<sup>st</sup> groups to reach out to private property owners in these neighborhoods, and ask them if they would consider adding a tree on their own private property (if conditions did not allow a tree to be planted in the street right-of-way along their frontage). Since 2009, the City has planted more than 1,250 street trees using grants from CBT and DNR.

Ever since 2010, the City has provided materials and manpower to the Antietam-Conococheague Watershed Alliance (ACWA) to aid in their annual Stream Cleanup events. Working with Dave Biser, the founder and leader of ACWA, the City provides gloves, trash bags and receptacles, and other supplies that are used by volunteers during their events. In early 2017, ACWA members helped to remove debris and downed trees from a section of Hamilton Run near Brookline Avenue. The City sees this partnership as a beneficial and needed method to both involve the public, and to restore the health of a stream that is already on the 303(d) list of impaired waters. The City plans to continue support this effort indefinitely. More information on ACWA can be found on their website: <http://www.acwamaryland.org/>





## Certificate of Recycling

*This document certifies that the materials received and processed by Novotec Recycling, LLC on behalf of Imaan International Inc (Agency) on 11/29/2016 have been handled in accordance with all applicable state and federal guidelines and have been recycled properly, completely, and in an environmentally responsible manner. All intellectual property contained on disk, CDs, or other electronic media has been destroyed.*

Amount of material processed:

18,730	Unprocessed - TVs (non-console)
2,175	Unprocessed - TVs (console & woodgrain)
2,335	Unprocessed - Projection CRT TVs
1,230	Unprocessed - Monitors

A handwritten signature in black ink, appearing to be "Roland Inthisarn", is written over a light blue rectangular background.

Certified By:

Roland Inthisarn/ Operations Manager

Printed Name/ Title

Agency Address

3960 Groves Road  
Columbus, Ohio 43232

### List of Lots Recycled

Lot Number	IMA112916-1
B.O.L.	26222787
Invoice #	14607

**IMAAAN International Inc.**

**Headquarters**

112 Juliad Court Ste 101  
Fredericksburg, VA 22406

**Branch Office: HQ**

112 Juliad Court Ste 101  
Fredericksburg, VA 22406

TEL: 540-737-4500

FAX: 540-737-4501

**Inbound Order**

Date: 11/18/2016 2:26 PM

In - Order No: E1600005

Order Type: RP

Sub OrderType:Asset Recovery

Account Rep.: Kelsey May

Reference #:

Ref Order #:

Parent Order Name: Hagerstown MD Recycling Event

**Account Name: City of Hagerstown MD**

**Billing Address:**

1 East Franklin Street  
Hagerstown, MD 21740  
UNITED STATES  
Rodney Tissue  
2406753743

**Pickup Address:**

274 E Memorial Blvd  
Hagerstown, MD 21740  
UNITED STATES  
Rodney Tissue  
240-675-3743

**Deliver to Address:**

112 Juliad Court Ste 101  
Fredericksburg, VA 22406  
UNITED STATES  
Arfan Azhar  
540-737-4500

Product Name	Packaging	Estimate Qty	Qty Base	Estimate Net Weight	Weight Base	Price Rate	Price Base	Estimate Sub Total USD \$
CRT/TV	Palletized	0	Pallet	22,820.00	LB	0.0000	Weight	0.00
Flat Pannel TVs	Palletized	0	Pallet	1,190.00	LB	0.0000	Weight	0.00
Flat LCD Monitors	Palletized	0	Pallet	598.00	LB	0.0000	Weight	0.00
Speakers/VCR/DVR/DVD	Palletized	0	Pallet	3,186.00	LB	0.0000	Weight	0.00
Desktop Computers/ Laptops	Palletized	0	Pallet	2,974.00	LB	0.0000	Weight	0.00
Misc. (keyboard, mice, etc)	Palletized	0	Pallet	1,678.00	LB	0.0000	Weight	0.00
Printer/Scanner/Copier/Phone/Remote	Palletized	0	Pallet	3,224.00	LB	0.0000	Weight	0.00
CRT Monitor	Palletized	0	Pallet	3,346.00	LB	0.0000	Weight	0.00
Payment Terms: COD Price Terms: CNF Estimate Shipment Date: 11/21/2016 12:00 AM Notes:							<b>Esti. Total USD \$</b>	<b>0.00</b>

**Esti. Grand Total USD \$ 0.00**

IMAAAN International Inc.

Signature \_\_\_\_\_

Date \_\_\_\_\_

City of Hagerstown MD

Signature \_\_\_\_\_

Date \_\_\_\_\_

## **Illicit Discharge Detection & Elimination**

One of the biggest challenges in complying with NPDES Phase II regulations is the development of an Illicit Discharge Detection & Elimination Program. The goal of this program is to detect and identify any illegal discharges of pollutants into the City's storm drainage system, and to develop a means to eliminate these discharges to minimize pollution of downstream receiving waters.

The City completed mapping of the surface water and storm drainage system in 2012, and has created a GIS database to share this information with other departments. While we are constantly updating the database with new information (an ongoing task, given that there are always "surprises" and new discoveries in a system that has existed for more than 150 years), the base mapping gives a good picture of how storm water runoff is collected and conveyed to the various discharge points around the City. A sample sheet from the GIS mapping is attached. It is hoped that the GIS can be used to model the transport of stormwater (and the pollutants that it carries) from any point in the City to its ultimate discharge point.

A continuing part of this component was for the City to inspect stormwater management facilities and various storm drainage outfalls in an effort to detect any illegal or illicit discharges into the storm drainage system. The attached "Water Resources Map" depicts the major surface water features through the City, and also indicates the locations of eleven (11) "major" outfalls of a City storm drainage network into a receiving stream or drainage way that were inspected in 2017. These outfalls were prioritized for inspection because (a) the watersheds that drain to them are densely developed, (b) there is little or no stormwater management in these watersheds (meaning pollutants are likely not being filtered out/removed prior to discharge), and (c) most of them discharge directly into a stream or body of water. Aside from trash and debris at various locations, none of the inspected outfalls showed evidence of "illicit" discharges. The inspection reports for these outfalls are included at the end of this section.

This year (2017) is also the year when the City performs its triennial inspection of all stormwater management facilities, and reports the findings of these inspections to MDE. Inspectors visit each facility and assess its condition, noting the need for any structural repairs or maintenance. In addition, the inspectors are trained to identify and report any signs of illicit discharges such as waste oil, grease/fat, etc.; these suspected discharges are then tracked upstream from the facility in an attempt to identify their source. Over 200 facilities will be inspected during this cycle; the "Post-Construction Runoff Control" section of this report contains more information on this effort. There are a series of other outfalls throughout the City that are inspected periodically; however, most of them represent smaller, less developed neighborhoods, or the outfalls are downstream from stormwater management facilities that (hopefully) have provided some water quality management. The attached inspection reports describe the physical features of each outfall, and document the results of field observations at those locations.

Using a grant from the Chesapeake Bay Trust and the Maryland Department of the Environment, the City commissioned an assessment of Hamilton Run Watershed in order to develop a "Watershed Action Plan". The purpose of this effort was to document segments of the stream that have been degraded by land development and other factors, and to identify and prioritize stream segments for restoration projects. As part of the data collection effort for the assessment, consultants walked the entire length of Hamilton Run several times; in addition to identifying erosion and streambank degradation, the consultants were instructed to inspect each storm drainage outfall along the stream corridor for signs of illicit discharges or other issues. The consultants documented trash and debris at many locations, but did not report any definite signs of illicit discharges. More information on the Action Plan can be found on the City's website at: <http://www.hagerstownmd.org/1280/Hamilton-Run-Action-Plan>

In response to a review of the City's 2015-2016 Annual Report, and after discussions with MDE staff during audits and at meetings to discuss the new NPDES General Permit, the City is developing a plan to perform systematic inspections of different areas of the storm drainage network. The purpose of these inspections is to spot-check particular areas or neighborhoods around the City where the concentration of commercial, residential, or other land uses would likely increase the potential for illicit discharges. These inspections will involve opening manholes, drainage inlets, and junction boxes to assess the condition of the system, and to look for signs of pollutants or illicit discharges near those locations; if any pollutants are observed, the inspection will continue upstream to the next access location, in an attempt to narrow down the search for a source. Two "target" areas have been identified for inspection during the 2017-2018 reporting period:

#### 2017 - 2018 Illicit Discharge Inspection – Area A: Burhans Blvd / West End

This area, corresponding to Grid Square #37-22 on the City's storm drainage system map, covers 200 acres of land just to the west of the downtown core. Included in this area are retail, commercial, and restaurant uses along the Burhans Blvd. corridor, along with a portion of the densely-developed West End residential neighborhood. Runoff from this area generally flows from northwest to southeast, toward Burhans Blvd. The storm drainage system maps for this area show more than 100 drainage inlets and manholes on this part of the system, which should provide many opportunities for access and inspection. This section of the City also contains some of the larger brick arch drains, which served as major underground stormwater conveyance structures when this neighborhood was developed 150 years ago.

#### 2017 - 2018 Illicit Discharge Inspection – Area B: Wesel Blvd.

This area, corresponding to Grid Square #49-7, covers another 200-acre area of land along the Wesel Blvd. corridor. This area consists of a regional shopping center, with outparcels containing restaurants, automobile service centers, and retail spaces. Runoff from these areas generally flows westward, to be managed in stormwater management ponds near the existing Sam's Club and Lowe's sites. This whole corridor was developed in the early to mid-1990's when Wesel Blvd. was constructed, and is served (for the most part) by pre-2000 era stormwater facilities. The City has previously cited at least one restaurant in this area for illicit discharges of grease and oil, and there are a number of commercial dumpster enclosures that will be inspected to ensure that any contaminated runoff is being contained.

Aerial photographs of these two target areas, along with the corresponding storm drainage system maps, are included on the following pages.



**2017 - 2018 STORM ILLICIT DISCHARGE INSPECTION  
AREA A - BURHANS BLVD./WEST END  
(GRID SQUARE 37-22)**




-  Index Grid
-  Buildings
-  Streams
-  Bridge
-  Outlet
-  Circular Inlet
-  Combination Inlet
-  Curb Inlet
-  Grate w. Manhole
-  Grate Only
-  Yard Inlet
-  EndSection
-  Open Pipe End
-  Headwall / Endwall
-  Junction Box
-  Manhole
-  Box Culvert
-  Brick Arch Drain
-  Storm Drain Pipe
-  Open Channel
-  Stormwater Pond
-  Roadway
-  Corporate Boundary



**37-22**

Scale : 1" = 300'





**2017- 2018 STORM ILLICIT DISCHARGE INSPECTION  
AREA B - WESEL BLVD.  
(GRID SQUARE 49-7)**




-  Index Grid
-  Buildings
-  Streams
-  Bridge
-  Outlet
-  Circular Inlet
-  Combination Inlet
-  Curb Inlet
-  Gate w. Manhole
-  Gate Only
-  Yard Inlet
-  EndSection
-  Open Pipe End
-  Headwall / Endwall
-  Junction Box
-  Manhole
-  Box Culvert
-  Brick Arch Drain
-  Storm Drain Pipe
-  Open Channel
-  Stormwater Pond
-  Roadway
-  Corporate Boundary



**49-7**

Scale : 1" = 300'



The general public is encouraged to report illicit discharges to the City so that they can be investigated. In addition to telephone calls to our offices, citizens can also report issues through the “Illicit Discharge Report” form on the City’s website:

### Pollutants

There are many different types of pollutants that are commonly found in stormwater runoff, including:

- Oil, grease, and antifreeze from automobiles and other machinery
- Fertilizer and pesticides from lawns, gardens, athletic fields, and agricultural fields
- Sediment from construction sites, mining operations, and farm fields
- Improperly disposed of household chemicals (detergents, cleaners, and solvents)

If you witness or discover a discharge of pollutants into the City’s storm drainage system, or into a stream or waterway, please report this information using the [Illicit Discharge Report Form](#).

The screenshot shows a web form titled "Illicit Discharge Reporting" with a breadcrumb "Home > Forms". The form contains the following fields:


- First Name\*
- Last Name\*
- House Number\*
- Street Name\*
- Telephone Number\*
- E-mail address\*
- Location of problem that you are reporting\*
- Description of problem that you are reporting\*
- Preferred contact method\* (dropdown menu with "e-mail" selected)

A red asterisk at the bottom indicates that fields marked with an asterisk are required.

The City has several methods to investigate and deal with illicit discharges. Within the public right-of-way, Chapter 216 of the City Code (<http://www.ecode360.com/9908267> “Streets and Sidewalks”) contains regulations that prohibit the leakage of loads from vehicles, deposition of mud or other materials on a street or alley, placement or leaves or grass clippings in the right-of-way, and the discharge of water (other than roof drainage, surface runoff, or utility repair) into the right of way. The penalties for these offences include a Municipal Infraction Citation and a fine of \$100 - \$200.

On private property, Chapter 64, Article III of the City Code (“Property Maintenance”) allows right-of-entry to Code Compliance inspectors to investigate “nuisances”, and includes a citation procedure to compel the property owner to correct or abate any violations. Chapter 240 (“Water Pollution Control”) also states that “...inspectors and other duly authorized employees of the City bearing proper credentials and identification shall be permitted to enter all properties at any reasonable time, to inspect users generally for compliance, to inspect and copy records and to require the installation of monitoring and sampling equipment.” Staff from the Code Compliance, Engineering, Wastewater, and Public Works Departments identify and report illicit discharges to the office of the City Engineer.

The City enjoys a good working relationship with staff at Washington County and the Maryland State Highway Administration. When an issue arises where storm drainage facilities from one jurisdiction connect or discharge into a different jurisdiction, the involved entities contact each other to review the issue, and to determine which entity has the responsibility of correcting the situation.



- 2017 OUTFALL INSPECTION LOCATIONS**
- 1 TOWN RUN
  - 2 MARSH RUN
  - 3 MARYLAND AVE./ DOWNSVILLE PIKE
  - 4 CITY PARK/ MAGGIE'S HOLE
  - 5 VALLEY ROAD
  - 6 NORTHERN AVENUE/AMERICAN LEGION
  - 7 MAGNOLIA AVENUE
  - 8 MONET DRIVE
  - 9 EAST FRANKLIN ST.
  - 10 WEST MEMORIAL BLVD.
  - 11 REST HAVEN CEMETERY
- City Corporate Boundaries  
 Outfall watershed boundaries

NOTES: Digital Base - F00

CITY OF HAGERSTOWN, MARYLAND ENGINEERING DEPARTMENT	
LOCATION City of Hagerstown	
TITLE WATER RESOURCE MAP NPDES PHASE II	
DRAWN BY T.Williams	DATE
Revision	DATE
SCALES   HORIZ: 1" = 1000'	VERTICAL:
DATE	APPROVED
BY CITY ENGINEER	FILE NUMBER 73-102-01

### Outfall Name: Town Run

Location: Municipal Stadium, just upstream from junction with Marsh Run  
NAD 83 Coordinates: N 716,634 E 1,111,337



**Description:** At this location Town Run is contained in a manmade channel; it is essentially the downstream end of the City's storm drainage system that serves the downtown area (and neighborhoods to the northeast). There is often a trickle of base flow in the channel, which is attributed to groundwater entering the storm drainage system at some point upstream. Because this channel receives the bulk of the runoff from the downtown section of the City, storm flow volumes and velocities at this location are high.

**Observations:** Outfall was inspected in the morning of May 21, 2016. The ambient temperature was in the low-60's, and the weather was partly cloudy. The last measurable rainfall event was on May 13<sup>th</sup>, when approximately 0.25 inches of rain was recorded.

No odors, or obvious signs of oil or similar pollutants. A significant amount of trash/litter in the channel. Slightly more baseflow in the invert of the channel, which was unusual given the time since the last rainfall; staff followed the channel upstream, looking for the source of the increased baseflow, but was unable to find anything before the channel switched into the closed underground drainage system. The City Water Department was notified, and planned to sample the water to determine if the increase flows were the result of a water main leak. Typical algae growth in the invert of the channel.

**Outfall Name: Marsh Run**

Outfall Location: Eastern Blvd. & Memorial Blvd., just upstream from Antietam Cr.  
NAD 83 Coordinates: N 716,134 E 1,112,127



**Description:** This is the downstream end of the box culvert Eastern Blvd. that is the discharge point for the combined Marsh Run/Town Run drainage system; the Town Run observation point is approximately 800' upstream from this location. Discharges from this culvert, which is adjacent to the former Municipal Electric Light Plant (MELP) facility, flow through an open stream channel to join Antietam Creek. There is perennial base flow at this location from the Marsh Run leg, which collects runoff the City Park area and the western portion of the City.

**Observations:** Outfall was inspected on the morning of May 21<sup>st</sup>; weather was partly cloudy, and temperatures were in the low-60's. The last previous precipitation event was approximately 0.25 inches of rain on May 13<sup>th</sup>. Baseflow at outfall was approximately 12.0' wide and 0.50' deep. Water appeared clear, with no obvious signs of pollutants or contaminants. Significant amount of trash/litter at this location. The majority of the adjacent MELP facility has been demolished; however, there is still demolition equipment present, and the erosion and sediment control facilities are still in place around the demolition site.

**Outfall Name: Maryland Avenue/Downsville Pike**

Outfall Location: Maryland Avenue, near its intersection with Downsville Road, adjacent to South End Shopping Center and South Hagerstown High School  
NAD 83 Coordinates: N 714,037 E 1,106,220




**Description:** This outfall consists of two CMP's (shown above) that discharge into a concrete-lined open channel; the channel carries flows downstream to the Maryland Avenue/Downsville Road intersection, where they enter a closed system that runs under the South High football field. This outfall is the discharge point for the storm drainage system that collects runoff from the Virginia Avenue/ Wilson Blvd. area on the south side of Hagerstown; the outfall pipes are undersized given both the size of the contributing drainage area and the size of the drainage pipes upstream. This channel also receives runoff from the parking lots at the adjacent South End Shopping Center, which have no stormwater management controls. Discharges at this point flow downstream through the South Hagerstown High School property, under MD Route 65, and eventually into the Antietam Creek near Funkstown.

**Observations:** Outfall was inspected on the morning of May 21st. Weather was partly cloudy, with temperatures in the low 60's. The last previous rain was approximately 0.25 inches on May 13<sup>th</sup>. No baseflow at the outfall; some trash, debris, and grass clippings in the concrete channel, but no sign of illicit discharges upstream. This site would be a good candidate for a stormwater retrofit facility to treat the runoff from the adjacent parking lots.

**Outfall Name: City Park/Maggie's Hole**

Outfall Location: City Park, near the Antietam Street/Walnut Street intersection  
NAD 83 Coordinates: N 720,477 E 1,107,554



**Description:** Outfall consists of a 12' x 5.5' box culvert at the railroad tracks that discharges into an open channel. This outfall is the discharge point for the extensive storm drainage system that collects and conveys runoff from the west end of Hagerstown. Discharges flow downstream through City Park, are conveyed along Memorial Blvd. through a collection of open channels and box culverts, and join the Town Run discharges near the MELP facility. The outfall site is encircled with fencing to prevent

**Observations:** Outfall was inspected in the afternoon of May 21<sup>st</sup>. Weather was partly cloudy, and temperatures were in the low to mid-60's. Last previous precipitation event was approximately 0.25 inches of rain on May 13<sup>th</sup>. Baseflow at this outfall was measured to be 6.0' wide and approximately 1/4" deep. No odors or other signs of pollutants or illicit discharges; tremendous amount trash and debris along the stream banks, and piled up along the perimeter fencing. Parks Department staff were notified to clean up trash.

**Outfall Name: Valley Road**

Outfall Location: Fairgrounds Park/American Little League field

NAD 83 Coordinates: N 722,569 E 1,113,474



**Description:** This outfall is the discharge point for the section of the City’s storm drainage system serving the neighborhoods north and east of Fairgrounds Park. The discharge point itself consists of a 48” diameter reinforced concrete pipe, which outlets into a channel with a series of very rough limestone outcroppings that serve to dissipate the energy of the runoff as it flows downstream. As mentioned previously, this channel leads to a section of “stream” that was restored as part of the Valley Road Stream Restoration project, and then to Hamilton Run approximately 800’ downstream from the outfall.

**Observations:** Outfall was inspected on the morning on May 22<sup>nd</sup>. Weather was partly cloudy, and the temperature was in the mid-60’s. The last previous precipitation event was approximately 0.25 inches of rainfall on May 13th. No baseflow from culvert; this is typical for this location. No observed pollutants in the culvert, or in the energy dissipation apron immediately downstream

**Outfall Name: Northern Avenue/American Legion**

Outfall Location: Northern Avenue on the east side of the American Legion property  
NAD 83 Coordinates: N 727,837 E 1,113,338



**Description:** This outfall is the discharge point for the section of the City's storm drainage system serving the Belview Avenue/Woodland Way neighborhood in the north end of Hagerstown. The discharge point itself consists of a 48" diameter CMP, which outlets directly into Hamilton Run. The alignment of the pipe at the discharge point has led to severe erosion of the adjoining streambanks; the City is preparing plans for a stream stabilization/restoration project at this location, and has sought financial assistance from MDE and DNR to complete the project. The Belview neighborhood is known to have a high groundwater table; consequently, there is often base flow being discharged from the pipe.

**Observations:** Outfall was inspected on the morning on May 22<sup>nd</sup>. Weather was partly cloudy, and the temperature was in the mid-60's. The last previous precipitation event was approximately 0.25 inches of rainfall on May 13th. The invert of the culvert was submerged, but it appeared to be caused by backflow/pooling of Hamilton Run, not baseflow discharges from the culvert. No odors or pollutants observed; a turtle and a few minnows swam by during the inspection.

**Outfall Name: Magnolia Avenue**

Outfall Location: Northern Avenue on the east side of the American Legion property  
NAD 83 Coordinates: N 725,603 E 1,115,807



**Description:** This outfall is the discharge point for storm drainage from the Potomac Heights/Calvert Terrace neighborhood in the City's north end. There are actually few storm drains in the neighborhood; runoff is conveyed in the gutter lines along the various streets until they intersect with Magnolia Avenue; a 36" RCP storm sewer trunk line then conveys this runoff to Hamilton Run. This site is problematic for the City's Public Works Department, as the multiple culverts that carry Hamilton Run under Magnolia Avenue (to the right in this photo) are prone to clogging with debris; this often causes minor flooding of the roadway and adjoining properties.

**Observations:** Outfall was inspected in the afternoon of May 22<sup>nd</sup>. Weather was partly cloudy, and the temperature was approximately 70 degrees. The last previous precipitation event was approximately 0.25 inches of rainfall on May 22<sup>nd</sup>. There was no base flow out of the 36". No evidence of pollutants, but the staining on the interior of the pipe suggests the potential for past oil/grease pollution; follow-up inspections of this site, particularly during a runoff event, are warranted. On the upstream side of the roadway culverts, a tree trunk has completely blocked one of the culverts; Public Works was notified, and will clear the channel within the next two week.

**Outfall Name: Monet Drive**

Outfall Location: Northern Avenue on the east side of the American Legion property  
NAD 83 Coordinates: N 723,227 E 1,114,085



**Description:** This outfall is the discharge point for relatively small drainage area in the north end of Hagerstown; storm drains and open channels convey stormwater to a stone box culvert under an elevated CSX railroad line; after exiting the culvert, storm flows travel approximately 400 feet to Hamilton Run, entering the stream adjacent to Pangborn Park.

**Observations:** Outfall was inspected on the afternoon of May 22<sup>nd</sup>. Weather was partly cloudy, and the temperature was approximately 70 degrees. The last previous precipitation event was approximately 0.25 inches of rainfall on May 13<sup>th</sup>. There was no base flow out of the box culvert; however, the grass in the receiving channel downstream from the culvert was flattened, indicating that some significant flows are discharged at this location. No evidence of pollutants, but some trash and litter were observed in and near the culvert.

**Outfall Name: East Franklin Street**

Outfall Location: Eastern end of E. Franklin Street adjacent to golf course  
NAD 83 Coordinates: N 719,340 E 1,113,720



**Description:** This outfall is the discharge location for a relatively small drainage watershed at the eastern end of East Franklin Street; immediately across the stream (Hamilton Run) from the discharge point is the City's municipal golf course. The outfall consists of a 21-inch CMP – a flap gate or backflow prevention device is attached to the end of the culvert, to prevent surcharges in this drainage system when there are larger storm flows in Hamilton Run.

**Observations:** The outfall was inspected on the afternoon of May 22<sup>nd</sup>; the temperature was approximately 72 degrees, and the weather was cloudy. The last recorded rainfall prior to this inspection was approximately 0.25 inches on May 13<sup>th</sup>. No odors or contaminants observed, and no trash visible stuck to the flap gate. The end of the 21-inch CMP is elevated approximately 18 inches above the stream; although it does not necessarily appear that significant erosion has occurred at this site, installation of a riprap apron or other outfall protection should be considered

**Outfall Name: West Memorial Boulevard**

Outfall Location: Northern Avenue on the east side of the American Legion property

NAD 83 Coordinates: N 717,083 E 1,110,828



**Description:** This outfall is the discharge point for the Chestnut Street storm drainage system, which collects runoff from a large portion of the City's South End, between Wilson Blvd. and Memorial Blvd. The discharge point consists of a 48" RCP that penetrates through the stone walls that form the Marsh Run aqueduct; a 45-degree elbow on the end of the pipe aligns discharges with Marsh Run's direction of flow. The invert of the culvert is slightly below the water level in the aqueduct, so there is some backflow from the stream into the end of the pipe. This discharge location is very near to the Public Works headquarters, and is inspected/observed frequently during storm events.

**Observations:** Outfall was inspected on May 21<sup>st</sup>. The last previous precipitation event was approximately 0.25 inches of rainfall on May 13<sup>th</sup>. There was no baseflow in the culvert, which was verified by inspection of the first upstream inlet at the intersection of Chestnut Street and Alley 2-109. No evidence of pollutants but, given the configuration of the outfall, it can be difficult to determine whether any pollutants observed downstream are coming from this drainage system, or the Maggie's Hole/Marsh Run leg of the stream.

**Outfall Name:** Rest Haven Cemetery  
**Outfall Location:** Interior of the Cemetery, directly north from Glenwood Avenue  
**NAD 83 Coordinates:** N 729,793 E 1,109,089



**Description:** This outfall is the discharge point for storm drainage from a small watershed along Glenwood Avenue and Haven Road. Runoff is collected in the system and conveyed by a 12" RCP into the cemetery grounds, where it discharged into Hamilton Run near its headwaters.

**Observations:** Outfall was inspected May 22<sup>nd</sup>. Weather was partly cloudy, and the temperature was approximately 70 degrees. The last previous precipitation event was approximately 0.25 inches of rainfall on May 13<sup>th</sup>. No base flow from the culvert, and no evidence of pollutants. This is a very visible discharge location in the center of the cemetery, and is under continual observation by the cemetery groundskeepers. The last few sections of culvert are adjacent to a large sycamore tree, and it is likely that the tree roots have attempted to infiltrate the pipe. Given the limited space to work between the existing grave plots in the cemetery, we have asked the Wastewater Department to run their CCTV camera through the system to identify potential structural issues that may need to be addressed.

## **Construction Site Runoff Control**

Construction site runoff is a significant threat to the quality of our streams and rivers. Uncontrolled runoff from construction sites allows mud and sediment to be transported onto adjoining properties, and into storm drains and drainage channels. Improper stabilization of disturbed areas leads to erosion and additional sediment pollution.

Chapter 209 of the Hagerstown City Code sets the requirements for erosion and sediment control for all projects in the City; the code can be viewed here: <http://www.ecode360.com/9907774> or by linking through the City's website [www.hagerstownmd.org](http://www.hagerstownmd.org). The code states that any project disturbing more than 5,000 square feet of earth must prepare a soil erosion and sediment control plan. Chapter 209 was revised to comply with the 2011 regulations, and was adopted in 2012.

For projects in the City of Hagerstown, the soil erosion and sediment control plan must be reviewed and approved by the Washington County Conservation District before a grading permit or building permit is issued. Denise Price is the local SCS plan review officer.

The City Code also delegates enforcement of the soil erosion and sediment control plan to the Maryland Department of the Environment. After a plan is approved and a grading permit is issued, the contractor is required to schedule a pre-construction meeting with the MDE enforcement officer. The MDE officer then monitors the site periodically during construction to ensure that the contractor is complying with the requirements of the plan and the grading permit.

The City has enjoyed a good working relationship with the MDE enforcement staff. Whenever the City has brought erosion and sediment control complaints to the attention of MDE (e.g. mud being tracked onto streets, improper silt fence installation, etc.), the actions of the enforcement officer have been very timely and responsive. Given the accelerated pace of development around the City in the early part of this decade, the control of construction site runoff has become a critical element in the stormwater pollution prevention program. The City looks forward to continuing this working relationship with the Washington County Conservation District and MDE.

## **Post-Construction Runoff Control**

Post-construction runoff control, or what most people refer to as “stormwater management”, is one of the most important elements in an overall pollution prevention program. As more and more farmland and open spaces are disturbed, and as more and more impervious surfaces are created, the quantity and quality of the runoff from these sites must be controlled to protect downstream properties and streams.

With the implementation of Environmental Site Design (ESD) regulations, developers must develop strategies to mimic pre-development hydrologic conditions from the earliest concept designs, and design their developments to minimize the impact on existing resources and drainage patterns. However, given challenging economic conditions, there has been limited commercial and residential development in the City over the past few years (although there are signs of some renewed development activity).

The City revised Chapter 213 of the City Code (the Stormwater Management Ordinance) to comply with these new regulations and, after receiving approval from MDE, moved to adopt the new ordinance; Chapter 213 can be viewed here: <http://www.ecode360.com/9907887> , or by clicking on the “City Code” link on the City’s website [www.hagerstownmd.org](http://www.hagerstownmd.org) .

In general, the Code requires all new projects to comply with the Maryland Department of the Environment’s Stormwater Act of 2007, and the implementation of the previously described ESD requirements.

For many years, the City has considered the implementation of a Stormwater Utility to help finance the anticipated inspection and maintenance programs. The comprehensive mapping of the storm drainage system mentioned in the “Illicit Discharge Detection” section of the report, along with analyses of existing impervious coverage in the City, will be an important element in the development of any such Utility. The City Council has now directed staff to solicit proposals from engineering consulting firms to begin development of such a utility; it is anticipated that a consultant will be selected to begin work on this project in early 2018.

An applicant wishing to perform a project in the City must submit a stormwater management report to the City Engineer for review and approval. The City Engineer and his staff review the report to ensure that the proposed design complies with the Code. The City requires that these stormwater reports are prepared by licensed engineers familiar with the principles and techniques of stormwater management. Upon approval of the plan, the City issues a stormwater management permit for the project; the City also requires the Applicant to enter into a Stormwater Management Maintenance Agreement with the City. Unlike Washington County and some other jurisdictions, the City does not take ownership of the stormwater management facilities after construction. The City also requires the Applicant to submit as-built plans of the facilities at the end of construction.

The City’s Engineering Division staff maintains a database of permitted stormwater management facilities. All stormwater facilities in the database are inspected on a rotating, three-year schedule; however, our inspectors often perform unscheduled inspections of facilities throughout the year, and respond to problems (e.g. sinkholes, erosion, etc.) as they arise. If an issue is identified during an inspection, a “Deficiency Notice” is mailed to the owner of the facility; a copy of a typical notice is attached. The Inspector performs a follow-up inspection to ensure that the work has been completed, and issues second notices as necessary. Through the Stormwater Management Maintenance Agreement that each facility owner must execute, the City has the authority to abate any continued violations, and place a lien upon the property until the owner reimburses the City for the work.

It happens that 2017 was the year when triennial inspections were due for the stormwater management facilities. Staff completed inspections of approximately 235 stormwater facilities; out of those, the City sent out seventy (70) Deficiency Notices to property owners to correct issues or properly maintain their facilities. An abridged copy of the inspection database is attached. The next full round of inspections is scheduled for 2020; however, staff will be conducting interim inspections at many of the facilities (especially the ones with deficiencies during the current inspection cycle) in 2018 and 2019.

In 2015 the City received a grant from the Chesapeake and Atlantic Coastal Bays Trust Fund to construct two stormwater management retrofit facilities to treat runoff from City-owned properties; more information on these facilities can be found in the "Pollution Prevention/Good Housekeeping" section of the report. In 2016, the City also received a Watershed Assistance Grant from MDE/Chesapeake Bay Trust to prepare a Watershed Action Plan for the Hamilton Run watershed. The Action Plan, completed in early 2017, identified and prioritized potential stream stabilization and restoration projects for future construction. In June 2017, the City was notified that it had been awarded a Green Streets-Green Jobs-Green Towns (G3) grant from EPA and the Chesapeake Bay Trust to construct two small retrofit stormwater facilities along Belview Avenue; the City plans to construct these facilities in the spring of 2018.

UNIQUE_ID	NORTH (M)	EAST (M)	DEVELOPMEN	ADDRESS	OWNER	STRU_TYPE	MAINT_AGRM	Status	LastInspection	Inspector	Actions	InspectionDate
SWMBBP1	220028.4	337692.28	BURHANS BLVD PLAZA	N BURHANS BLVD & W FRANKLIN ST	R M PLAZA LLC - C/O MICHAEL BYERS - 8858	IT	NONE	Satisfactory	7/31/2014	ZDR	Send Letter	6/27/2017
SWMBBP2	220028.4	337692.28	BURHANS BLVD PLAZA	N BURHANS BLVD & W FRANKLIN ST	R M PLAZA LLC - C/O MICHAEL BYERS - 8858	IT	NONE	Satisfactory	7/31/2014	ZDR	Send Letter	6/27/2017
SWMBRMAN1	221653.49	337752.41	BRIGHTON MANOR	W IRVIN AVE & WAYNE AVE	STAMPER MILTON	DP	ON FILE 5/20/88	Satisfactory	4/30/2014	ZDR	None.	6/28/2017
SWMHOMADD	217255.61	338142.51	HOMELAND ADDITION	E WILSON BLVD	NOT LISTED	IT	NONE	Satisfactory	7/31/2014	ZDR	None	11/16/2017
SWMPNGHTS2D	220146.64	340187.65	PANGBORN HEIGHTS	SECURITY RD	STAMPER ANDY	SM	ON FILE 6/8/90	Satisfactory	6/9/2014	ZDR	None	7/7/2017
SWMWPC1	217000.11	339151.21	WPC PELLETTIZING PLANT	FREDERICK ST	WPC	IT+DP	NONE	Satisfactory	8/7/2014	ZDR	None	6/30/2017
SWMWPC2	217000.11	339151.21	WPC PELLETTIZING PLANT	FREDERICK ST	WPC	IT+DP	NONE	Satisfactory	8/7/2014	ZDR	None	6/30/2017
SWMRMDWS	217018	340865.34	ROLLING MEADOWS	MOUNT AETNA RD	CHURCHEY WES	IT+DP	6/26/88 & 3/30/89	Satisfactory	8/1/2014	ZDR	None	12/5/2017
SWMPINCRST	218092.58	335960.54	PINECREST EXTENSION	PINECREST AVE	CITY OF HAGERSTOWN DPW	IT	PER 12/27/91 MEMO BY	Satisfactory	8/1/2014	ZDR	None	11/6/2017
SWMHGBSPK5	218465.82	336486.46	HAGERSTOWN BUS PK	S BURHANS BLVD	CITY OF HAGERSTOWN DPW	ED	NONE	Satisfactory	8/5/2014	ZDR	None	10/18/2017
SWMADINC1	220518.37	338923.59	ADVERTISING INC	McCOSMUS ST & POTOMAC AVE	REYNOLDS WILLIAM	IT	ON FILE 1/20/92	Satisfactory	8/1/2014	ZDR	None	10/18/2017
SWMWAMUFA	218659.94	337060.68	WASHINGTON CO MUSEUM OF FINE ARTS	MUSEUM DR	CITY OF HAGERSTOWN DPW	OGS	REC L 1154 F 0957	Satisfactory	7/24/2014	ZDR	None	7/7/2017
SWMENGLPRK	216952.06	340639	ENGLBROOK PARK TH	CHANTILLY CT & LANGLEY DR	CHURCHEY WES	DP	NONE	Satisfactory	7/4/2014	ZDR	None	10/10/2017
SWMCTRANT1	218444.33	339771.14	CENTRE AT ANTIETAM CREEK - THE	DUAL HWY & EASTERN BLVD N	HARRISON TIMOTHY	DP	REC L 1595 F 0206	Deficiency	7/17/2014	ZDR	Send Letter	10/10/2017
SWMPNGHTS2B	220204.82	340129.73	PANGBORN HEIGHTS	LYNNEHAVEN RD	SHAOOL BEN	DP	REC L 1595 F 0170	Satisfactory	6/10/2014	ZDR	None	7/7/2017
SWMPNGHTS2C	220204.82	340129.73	PANGBORN HEIGHTS	LYNNEHAVEN RD	SHAOOL BEN	DP	REC L 1595 F 0170	Satisfactory	6/9/2014	ZDR	None	7/7/2017
SWMCTR HAG1	220894.05	335414.38	CENTRE AT HAGERSTOWN - THE	GARLAND GROH BLVD & US-40	WASH REAL ESTATE INVEST TRUST	DP	REC L 1477 F 0727	Deficiency	7/3/2014	ZDR	Send Letter.	6/28/2017
SWMHAGCOMS	216664.14	340538.06	HAGERSTOWN COMMONS	DUAL HWY & EDGEWOOD DR	McCLEARY DICK	ED	REC L 1154 F 0926	Under Construction		ZDR	None	6/26/2017
SWMHAGPLZ1	221823.02	336080.16	HAGERSTOWN PLAZA	18053 GARLAND GROH BLVD	UNIWEST GROUP, LLC.	WP	ON FILE 09/21/06	Deficiency	7/3/2014	ZDR	Send Letter	7/3/2017
SWMPOTMNR1	220811.96	340189.04	POTOMAC MANOR	DAYSRING DR	HOME CONSTRUCTION CORP OF HAG	DP	NONE	Satisfactory	6/9/2014	ZDR	None	12/5/2017
SWMERDGTH1	218350.47	338985.68	EAST RIDGE	EASTERN BLVD & E RIDGE DR	PEARL STEVE	DP	ON FILE 3/30/05	Satisfactory	8/5/2014	ZDR	None	10/24/2017
SWMERDGTH2	218350.47	338985.68	EAST RIDGE	EASTERN BLVD & E RIDGE DR	PEARL STEVE	BIO+WQ	ON FILE 3/30/05	Satisfactory	8/5/2014	ZDR	None	10/24/2017
SWMFARCHL DHT	221848.96	338214.49	FAIRCHILD HEIGHTS	FAIRCHILD AVE	R & J BUILDERS	DP	ON FILE 7/19/04	Deficiency	4/30/2014	ZDR	None.	6/26/2017
SWMHCPH2A	221340.87	334343.04	HAGERS CROSSING PHASE II	FALLING TIMBERS CIRCLE	FAIRMOUNT REAL ESTATE SERVICES, LLC.	ED	ON FILE 7/19/07	Satisfactory	7/4/2014	ZDR	None	12/5/2017
SWMHCPH3	221775.46	334762.88	HAGERS CROSSING PHASE III	HAGERS CROSSING DR.	FAIRMOUNT REAL ESTATE SERVICES, LLC.	ED	ON FILE 3/16/06	Deficiency	6/14/2014	ZDR	Send Letter. See	6/28/2017
SWMHCPH1A	221168.7	334767.23	HAGERS CROSSING PHASE I	HAGERS CROSSING DRIVE	FAIRMOUNT REAL ESTATE SERVICES	DP	ON FILE 3/12/03	Deficiency	4/30/2014	ZDR	Send Letter with j	10/13/2017
SWMHCPH1B	221118.82	335054.28	HAGERS CROSSING PHASE I	HAGERS CROSSING DRIVE	FAIRMOUNT REAL ESTATE SERVICES	BIO	ON FILE 3/12/03	Deficiency	7/3/2014	ZDR	Send letter regard	10/16/2017
SWMCRTMANPH2B	222018.76	340475.01	CORTLAND MANOR PHASE II	HAWKINS CIRCLE	DAVID C. LYLES	WQ	AGREEMENT OUT DATE	Deficiency	6/13/2014	ZDR	Send Letter.	6/30/2017
SWMCRTMANPH2A	222338.24	340406.86	CORTLAND MANOR PHASE II	HAWKINS CIRCLE	DAVID C. LYLES	WQ		Under Construction		ZDR	None.	7/3/2017
SWMPOTMNR2	220805.15	340230.35	POTOMAC MANOR	HOLLYMEAD TERRACE	HOME CONSTRUCTION CORP OF HAG	DP	NONE	Under Construction		ZDR	None	6/30/2017
SWMCOLLEGIATE	222797.35	335983.47	COLLEGIATE ACRES	MAUGANSVILLE RD	BEAZER HOMES CORP., MARYLAND DIVISIO	ED	ON FILE 03/04/2008	Deficiency	6/10/2014	ZDR	None.	6/26/2017
SWMCRTMANPH3A	222057.59	340414.93	CORTLAND MANOR, PHASE III	MD RTE. 60	CORTPARK, LLC. - BEN SHAOOL, MEMBER	WQ+SF	ON FILE 1/05/05	Satisfactory	7/3/2014	ZDR	None	6/30/2017
SWMCRTMANPH3B	221817.98	344411.99	CORTLAND MANOR, PHASE III	MD RTE. 60	CORTPARK, LLC. - BEN SHAOOL, MEMBER	WQ+SF	ON FILE 1/05/05	Deficiency		ZDR	Follow up inspect	6/30/2017
SWMCRTMANPH3C	221730.78	340477.94	CORTLAND MANOR, PHASE III	MD RTE. 60	CORTPARK, LLC. - BEN SHAOOL, MEMBER	DP	ON FILE 01/05/05	Satisfactory		ZDR	None	7/13/2017
SWMPESCL	219082.98	339756.02	PANGBORN ELEMENTARY SCHOOL	PANGBORN BLVD	WASHINGTON COUNTY PUBLIC SCHOOLS	ED	ON FILE 4/11/07	Deficiency	7/29/2014	ZDR	Send Letter. See	7/17/2017
SWMDRFKLN1	220513.96	337952.54	DEERFIELD KNOLLS	PELETON STREET	REVERE DEVELOPMENT COMPANY	DP	ON FILE 4/17/07	Under Construction		ZDR	None. Not built	
SWMDRFKLN2	220801.93	337925.02	DEERFIELD KNOLLS	PELETON STREET	REVERE DEVELOPMENT, LLC.	DP	ON FILE 4/17/07	Under Construction		ZDR	None. Not Built	
SWMCRTMANPH1A	222347.37	340042.26	CORTLAND MANOR PHASE I	POTOMAC AVE	RIDER DAVID & DAVID LYLES	DP	REC L 1963 F 0228 AGM	Deficiency	7/14/2014	ZDR	Send letter about	6/30/2017
SWMCRTMANPH1B	222347.37	340042.26	CORTLAND MANOR PHASE I	POTOMAC AVE	RIDER DAVID & DAVID LYLES	WQ	REC L 1963 F 0228 AGM	Deficiency	7/14/2014	ZDR	Send Letter	6/30/2017
SWMSHSQ1	221903.02	339896.59	STONE HOUSE SQUARE - FAISON	12809 SHANK FARM WAY	FAISON-HAGERSTOWN, LLC.	ED	ON FILE 2/15/07	Deficiency	8/1/2014	ZDR	Send Letter.	6/30/2017
SWMSHSQ2	221932.02	339900.7	STONE HOUSE SQUARE - FAISON	12809 SHANK FARM WAY	FAISON-HAGERSTOWN, LLC.	ED	ON FILE 2/15/07	Deficiency	8/1/2014	ZDR	Letter Sent	6/30/2017
SWMCGBCHURCH	220517.02	336894.93	CALVARY GRACE BRETHERN CHURCH	WAKEFIELD RD	CALVARY GRACE BRETHERN CHURCH	DP	ON FILE 3-13-06	Satisfactory	7/31/2014	ZDR	None	6/30/2017
SWMSTAPLES	218167.55	334682.27	STAPLES	1020 HEISTER ST	STONERIDGE DEVELOPMENT CORP	DP	NONE	Satisfactory	7/24/2014	ZDR	None	
SWMLWHPH1	0	0	LINWOOD HOLLOW	WOODLAKE DRIVE	POPLAR SQUARE, L.L.C.	ED	ON FILE 7/19/07	Satisfactory	8/5/2014	ZDR	None	
SWMGATEWAY1	0	0	GATEWAY CROSSING		GATEWAY CROSSING HOUSING PARTNERS	IT	8/1/2002	Satisfactory	7/31/2014	ZDR	None	11/6/2017
SWMGATEWYPH4	0	0	GATEWAY CROSSING PHASE IV		GATEWAY CROSSING HOUSING PARTNERS	DP	NONE	Satisfactory	7/31/2014	ZDR	None	11/6/2017
SWMPOTTWR	219192.4	337960.35	POTOMAC TOWERS	11 W BALTIMORE ST	MIKE STONER-HAGERSTOWN HOUSING	UGS	NONE	Satisfactory	7/24/2014	ZDR	None	12/5/2017
SWMTRLUTH	219906.72	338476.75	TRINITY LUTHERAN CHURCH	15 RANDOLPH AVE	CODERMAN JOHN	DW	ON FILE 9/20/91	Satisfactory	7/31/2014	ZDR	None	11/15/2017
SWMISPM1	220386.83	338562.92	ISP MINERAL (GAF CORP)	34 CHARLES ST	ISP MINERAL CORP	IT	REC 1/18/91	Satisfactory	8/2/2014	ZDR	None	7/17/2017
SWMISPM2	220386.83	338562.92	ISP MINERAL (GAF CORP)	34 CHARLES ST	ISP MINERAL CORP	IT	REC 1/18/91	Satisfactory	8/1/2014	ZDR	None	7/17/2017
SWMCVS	219276.61	338687.28	CVS PHARMACY	34 N CANNON AVE	THOMASON BRAD	OGS	REC L 1963 F 0168 AGM	Satisfactory	8/1/2014	ZDR	None	11/9/2017
SWMANTACADEMY1	216326.31	336936.7	ANTIETAM ACADEMY	40 WEST OAK RIDGE	BOARD OF ED. WASHCO	SW	ON FILE 08/18/09	Satisfactory	7/18/2014	ZDR	Send Letter	7/3/2017
SWMANTACADEMY2	216372.24	336982.75	ANTIETAM ACADEMY	40 WEST OAK RIDGE DR.	BOARD OF ED. OF WASHCO	DP	ON FILE 08/18/09	Deficiency	7/18/2014	ZDR	Send Letter	7/3/2017
SWMANTACADEMY3	216342.22	336944.1	ANTIETAM ACADEMY	40 WEST OAK RIDGE DR.	BOARD OF ED. OF WASHCO	BIO	ON FILE 08/18/09	Satisfactory	7/18/2014	ZDR	None	7/3/2017
SWMANTACADEMY4	216432.84	336998.11	ANTIETAM ACADEMY	40 WEST OAK RIDGE DR.	BOARD OF ED. OF WASHCO	SF	ON FILE 08/18/09	Deficiency	7/18/2014	ZDR	None	7/3/2017
SWMELGIN	219884.65	337015.4	ELGIN STATION COMMUNITY CENTER	40 ELGIN BLVD	CITY OF HAGERSTOWN	DP	ON FILE 2/5/03	Satisfactory	7/4/2014	ZDR	None	7/3/2017
SWMBRYCTR1	219747.47	338114.11	BRYAN CTR	49 W FRANKLIN ST	BRYAN JIM	IT	ON FILE 11/5/92	Satisfactory	7/14/2014	ZDR	None	11/14/2017
SWMMKSBUS	218719.4	340099.49	M K S BUS PK	100 EASTERN BLVD N	McCLEARY DICK	DP	ON FILE 10/8/90	Satisfactory	7/3/2014	ZDR	Send Letter	11/3/2017
SWMEEFS	218719.4	340099.49	COMMUNITY RESCUE SERVICE	100 EASTERN BLVD N	COMMUNITY RESCUE SERVICES, INC.	DP	REC L 1595 F 0146,	Deficiency	7/10/2014	ZDR	None	11/3/2017
SWMHOF CAR1	216017.85	339530.91	HOFFMAN CAR DEALERSHIP	101 S EDGEWOOD DR	ZAYAS EDISON	DP	REC L 1200 F 0014	Satisfactory	7/24/2014	ZDR	None.	7/10/2017
SWMOUMCH	219522.55	338475.45	OTTERBEIN UNITED METH CHURCH	101 E FRANKLIN ST	CUMP GERALD	DW	REC L 1963 F 0206	Satisfactory	7/15/2014	ZDR	None	12/5/2017
SWMJJOEL	217685.71	337331.7	JOEL RICE	106 WEST WILSON BLVD	JOEL R. RICE	IT	ON FILE 4/15/03	Satisfactory	8/2/2014	ZDR	None	11/6/2017
SWMAL1	219986.23	338109.12	ADKINS LUBE	120 W CHURCH ST	ADKINS ORVILLE	IT	REC PLAT 2376	Satisfactory	8/1/2014	ZDR	None	11/14/2017

SWMBUSTRNSFR	219780.87	337963.72	WASHINGTON COUNTY BUS TRANSFER S1W FRAKLIN ST	WASHINGTON COUNTY	BIO	ON FILE 08/23/2010	Satisfactory	4/30/2014	ZDR	None	12/5/2017
SWMSS3	219720.72	338267.55	SOCIAL SERVICES 122-128 N POTOMAC ST	NOT LISTED	IT	NONE	Satisfactory	8/1/2014	ZDR	None	11/7/2017
SWMSS1	219720.72	338267.55	SOCIAL SERVICES 122-128 N POTOMAC ST	NOT LISTED	IT	NONE	Satisfactory	8/1/2014	ZDR	None	11/20/2017
SWMSS2	219720.72	338267.55	SOCIAL SERVICES 122-128 N POTOMAC ST	PERINI PAUL	IT	5/6/94 L 1200 F 0001	Satisfactory	8/1/2014	ZDR	None	11/20/2017
SWMCRCUR1	219847.04	338018.75	CHRIST REFORMED CHURCH 130 W FRANKLIN ST	WINEBRENNER WAYNE	BIO	AGMT 12/13/01 L 1963 F	Satisfactory	8/7/2014	ZDR	Send Letter	11/8/2017
SWMRCWHTUB1	219999.08	338029.4	CITY WASH TUB 145 W CHURCH ST	NOT LISTED	IT	NOT ON SITE PLAN	Satisfactory	8/1/2014	ZDR	None	11/8/2017
SWMCASSH	219062.37	338255.5	CASH LLC 145-147 E BALTIMORE ST	SWORD DARYL	IT	AGMT 6/1/01 L 1963 F 01	Satisfactory	8/1/2014	ZDR	None	11/14/2017
SWMKENSINGTON	218888.74	340144.23	KENSINGTON 151 EASTERN BLVD	KENSINGTON, LLC.	DP	ON FILE 3/8/04	Deficiency	7/17/2014	ZDR	Send Letter.	9/1/2017
SWMEAKLES	220194.29	337776	EAKLE'S DRUG STORE 201 N BURHANS BLVD	NOT LISTED	DW	NONE	Satisfactory	7/31/2014	ZDR	None	11/15/2017
SWMZION	219834.52	338338.84	ZION EVANGELICAL CHURCH 201 N POTOMAC ST	RIDENOUR WELSS	IT	ON FILE 8/5/91	Satisfactory	7/15/2014	ZDR	None	10/7/2017
SWMHBCHURCH	219274.37	337705.17	HAGERSTOWN BIBLE CHURCH 203 SUMMIT AVE	RICHARD SOWERS TRUSTEE	UGS	REC L 1595 F 0183	Satisfactory	8/1/2014	ZDR	None	11/14/2017
SWMCP1	218959.73	338318.22	CORNER PUB PARKING LOT 208-210 FREDERICK ST	SWORD VERNON	SW	AGMNT 3/11/94 L 1154 F	Satisfactory	8/2/2014	ZDR	None	11/15/2017
SWMCP2	218959.73	338318.22	CORNER PUB PARKING LOT 208-210 FREDERICK ST	SWORD VERNON	SW	AGMNT 3/11/94 L 1154 F	Satisfactory	8/2/2014	ZDR	None	11/15/2017
SWMSTMARY	219777.63	337810.47	SAINT MARY'S CHURCH 218 W WASHINGTON ST	REV WILLIAM KEEFER	IT	ON FILE 10/25/90	Satisfactory	7/31/2014	ZDR	None	12/5/2017
SWMONEILL	218712.59	338909.91	LORRAINE O'NEILL 225/227 N CLEVELAND	LORRAINE O'NEILL	UGS	ON FILE 6/2/03	Satisfactory	8/1/2014	ZDR	None	11/9/2017
SWMHOLEXP	218201.09	333857.88	HOLIDAY INN EXPRESS 241 RAILWAY LN	BOWMAN GROUP	DP+MP	REC L 1595 F 0235	Deficiency	7/24/2014	ZDR	Send Letter	7/17/2017
SWMHOOD	218651.52	338541.59	DR HOOD MEDICAL OFC 249 MILL ST	DR STEPHEN HOOD	DP	ON FILE 8/23/91	Satisfactory	7/31/2014	ZDR	None	7/30/2017
SWMWILMED	218603.78	338540.35	MILL ST MEDICAL CTR 265 MILL ST	FEDDER, DAVIS DEV GROUP	IT	ON FILE 7/31/89	Deficiency	7/31/2014	ZDR	Send Letter	11/8/2017
SWMPROVIL	218527.02	338416.98	PROFESSIONAL VILLAGE 300 MILL ST	NOT LISTED	DP	7/31/89	Satisfactory	7/29/2014	ZDR	None	6/28/2017
SWMBONDAP1	218785.86	338968.47	BONDED APPLICATORS 301 S CLEVELAND AVE	FRY ROBERT	DP	ON FILE 2/9/89	Satisfactory	8/2/2014	ZDR	None	7/27/2017
SWMSHEETZ	219216.91	338655.05	SHEETZ 301 E WASHINGTON ST	SHEETZ ROBERT	UGS+OGS	REC L 1200 F 0001	Satisfactory	7/30/2014	ZDR	None	11/7/2017
SWMCLEVCOMM	218756.66	338950.42	CLEVELAND AVENUE COMMONS 305-329 S CLEVELAND AVENUE		DP	NONE	Deficiency	8/2/2014	ZDR	Send Letter	7/27/2017
SWMAAUTO	219133.1	338771.75	ADVANCED AUTO PARTS 325 E. WASHINGTON AVE	B & P PROPERTIES	DP	ON FILE 1/21/06	Deficiency	8/2/2014	ZDR	Send letter.	7/21/2017
SWMSUPSHOE	218636.92	338420.42	SUPA SHOE 330 FREDERICK ST	NOT LISTED	IT	NONE	Satisfactory	7/30/2014	ZDR	None	11/16/2017
SWMJMNH1	218585.43	338331.58	JULIA MANOR NURSING HOME 333 MILL ST	PERINI PETER	IT+DP	REC L 1346 F 0580	Satisfactory	7/3/2014	ZDR	None	10/27/2017
SWMJMNH2	218585.43	338331.58	JULIA MANOR NURSING HOME 333 MILL ST	PERINI PETER	IT+DP	REC L 1346 F 0580	Satisfactory	7/3/2014	ZDR	None	10/27/2017
SWMDIAMOT	219299.04	338800.77	DIAMOND MOTORS 340 DUAL HWY	HAYNES JOHN	DP	REC L 1595 F 0220	Deficiency	7/31/2014	ZDR	Send Letter.	7/21/2017
SWMYORK	221486.78	336389.07	YORKSHIRE WOODS 343 YORKSHIRE DR	CITY OF HAGERSTOWN DPW	IT	PER 12/27/91 MEMO BY	Satisfactory	7/3/2014	ZDR	None	12/5/2017
SWMFARPRK	219685.79	339184.93	FAIRGROUNDS PARK 351 N CLEVELAND AVE	CITY OF HAGERSTOWN DPW	ED	CITY OF HAGERSTOWN	Satisfactory	7/3/2014	ZDR	None	12/15/2017
SWMBESTER1	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Deficiency		ZDR	Send Letter.	10/27/2017
SWMBESTER10	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Under Construction		ZDR	Send Letter	10/27/2017
SWMBESTER11	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Under Construction		ZDR	Send Letter	10/27/2017
SWMBESTER2	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Deficiency		ZDR	Send Letter.	10/27/2017
SWMBESTER3	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Satisfactory		ZDR	None	10/27/2017
SWMBESTER4	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Deficiency		ZDR	Send Letter.	10/27/2017
SWMBESTER5	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Deficiency		ZDR	Send Letter.	10/27/2017
SWMBESTER6	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Deficiency		ZDR	Send Letter.	10/27/2017
SWMBESTER7	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Deficiency		ZDR	Send Letter.	10/27/2017
SWMBESTER8	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Deficiency		ZDR	Send Letter.	10/27/2017
SWMBESTER9	218634.08	338134.78	BESTER ELEMENTARY SCHOOL 385 MILL ST	WASCHO BOARD OF EDUCATION	BIO	ON FILE 9/12/12 REC L 4	Satisfactory		ZDR	Send Letter	10/27/2017
SWMWDPNT	221668.09	336487.52	WOODPOINT MANOR 392 YORKSHIRE DR	CITY OF HAGERSTOWN DPW	IT	PER 12/27/91 MEMO BY	Satisfactory	7/15/2014	ZDR	None	10/4/2017
SWMWELD	218713.77	337688.7	COSS WELDING 400 W MEMORIAL BLVD	NOT LISTED	DP	NONE	Satisfactory	7/21/2014	ZDR	None	12/5/2017
SWMSTINE	218960.39	338799.84	STINE LEE E INC 401 E. ANTIETAM ST	STINE LEE	IT+DP	REC 7/11/95 L 1254 F 01	Satisfactory	8/2/2014	ZDR	None.	7/21/2017
SWMPARKPLAZA	219173.94	337185.89	PARK PLAZA 401 HIGHLAND AVE	PARK PLAZA PROPERTIES LLC	DP	NONE	Satisfactory	7/7/2014	ZDR	None	7/7/2017
SWMVENINN	219131.85	338882.74	VENICE INN 431 DUAL HWY	NOT LISTED	DP	NONE	Satisfactory	8/2/2014	ZDR	None.	12/15/2017
SWMWACOHUM	219431.2	336701.17	WACO HUMAN DEVELOPMENT 433 BREWER AVE	NOT LISTED	DP	NONE	Deficiency	7/30/2014	ZDR	Send Letter	7/7/2017
SWMSTORAGEBIN	218585.36	338748.2	THE STORAGE BIN 435 E. BALTIMORE ST.	JEFFREY A. SMITH	DP	ON FILE 01/06/09 REC L	Satisfactory	7/3/2014	ZDR	None	11/9/2017
SWMCASSTRU	218646.37	337926.83	CASSIDY TRUCKING 441 S POTOMAC ST	CASSIDY ELAINE	OGS	REC L 1154 F 0950	Satisfactory	8/1/2014	ZDR	None	11/14/2017
SWMTACO	219158.02	338944.75	TACO BELL 450 DUAL HWY	PAPHITES TASSOS	IT	ON FILE 4/23/92	Satisfactory	7/24/2014	ZDR	None	12/15/2017
SWMTACO2	219136.15	338978.95	TACO BELL 450 DUAL HIGHWAY	TASSOS PAPHITES	BIO	ON FILE 03/11/14 REC L	Satisfactory	8/1/2014	ZDR	None	12/15/2017
SWMBASSEM1	217345.72	338120.9	BETHEL ASSEMBLY OF GOD 515 E WILSON BLVD	HORST CLARENCE	DP	REC L 1595 F 0227	Satisfactory	7/31/2014	ZDR	None	9/29/2017
SWMSALVARMY1	220195.36	337554.08	THE SALVATION ARMY 525 GEORGE ST	THE SALVATION ARMY	BIO	ON FILE 03/11/14 REC L	Deficiency	7/31/2014	ZDR	None	6/26/2017
SWMSALVARMY2	220180.57	337543.75	THE SALVATION ARMY 525 GEORGE ST	THE SALVATION ARMY	BIO	ON FILE 03/11/14 REC L	Satisfactory	7/31/2014	ZDR	None	11/6/2017
SWMJDKITC	222058.55	339051.45	J & D KITCHENS 525 NORTHERN AVE	ABUUD DAHBURA/DOMINIC PERINI	IT	REC L 1154 F 0967	Satisfactory	7/3/2014	ZDR	None	11/16/2017
SWMHFL	220892.16	340710.03	HAGERSTOWN FIBER & LIGHT 551 EASTERN BLVD N	KAUFMANN ANDY	DP	REC L 1199 F 1040 4/14/9	Satisfactory	7/31/2014	ZDR	None	10/27/2017
SWMDEFNET	219570.16	339347.14	DEAFNET OF WASHINGTON CO 551 JEFFERSON ST	BIBLE HAROLD	DP	REC L 1963 F 0200 AGM	Satisfactory	7/31/2014	ZDR	None	7/21/2017
SWMGENBIND	219282.79	334493.7	GENERAL BINDING CORP 560 WESTERN MARYLAND PKWY	MARTIN DEAN	DP	REC L 1346 F 0621	Deficiency	7/31/2014	ZDR	Send Letter	7/14/2017
SWMCELL1	222122.31	338991.02	CELLULAR ONE 580 NORTHERN AVE	NORTHERN AVE REALTY ASSOCIATES	IT	NONE	Satisfactory	7/3/2014	ZDR	None	11/15/2017
SWMICESPRT	219784.04	339401.15	HAGERSTOWN ICE & SPORTS COMPLEX 580 SECURITY RD	CITY OF HAGERSTOWN DPW	ED	NONE	Satisfactory	5/5/2014	ZDR	Notify Parks and	12/15/2017
SWMWISEA	220874.67	337809.73	WISE AUCTION HOUSE 700 LINGANORE AVE	WISE HAROLD	DW	REC L 1595 F 0163	Satisfactory	7/3/2014	ZDR	None	10/4/2017
SWMPARKOVERLOC	220159.72	339598.11	PARK OVERLOOK TOWN HOMES 701 MONET DR	PDR PARADISE, LLC.	DP	ON FILE 10/8/03	Deficiency	6/13/2014	ZDR	Send Letter.	7/17/2017
SWMNIDDLESCHL	222103.88	338829.2	NORTHERN MIDDLE SCHOOL 701 NORTHERN AVE	WASHCO BOE	BIO	ON FILE 03/11/14 REC L	Satisfactory	7/14/2014	ZDR	None	6/28/2017
SWMCOPY	220559.05	338832.07	COPY QUICK 710 OAK HILL AVE	SHANK RICHARD	DP	AGMT 2/6/01 L 9963 F 01	Satisfactory	8/5/2014	ZDR	None	7/17/2017
SWMKENAPTS	217311.02	338722.56	KENLY APTS & SHOP CTR 715 KNIGHTSBRIDGE RD	BROWN ALTON	IT+DP	REC L 1220 F 0580	Satisfactory	7/3/2014	ZDR	None	12/15/2017

SWMBPUSA	217672.37	338660.13	BURGER PARK USA	812 FREDERICK ST	HOLLINGER RAYMOND	DW	ON FILE 7/18/88	Satisfactory	8/2/2014	ZDR	None	11/14/2017
SWMEMANUNI	218131.27	337216.13	EMMANUEL UNITED METH CHURCH	819 GUILFORD AVE	MONGAN NORMAN	DW	ON FILE 2/27/92	Satisfactory	7/31/2014	ZDR	None	11/16/2017
SWMPHMAR	217875.14	337588.44	PHIL MARSHALL AUTOMOTIVE	825 S POTOMAC ST	MARSHALL PHIL	UGS	2/4/92	Satisfactory	8/1/2014	ZDR	None	12/5/2017
SWMWACO1	220985.72	337669	WACO ARC	820-840 FLORIDA AVE	ARC OF WASHINGTON COUNTY	IT	REC L 1199 F 1048	Satisfactory	6/10/2014	ZDR	Send Letter.	7/3/2017
SWMWACO2	220985.72	337669	WACO ARC	820-840 FLORIDA AVE	ARC OF WASHINGTON COUNTY	IT	REC L 1199 F 1048	Deficiency	6/10/2014	ZDR	Send Letter	7/3/2017
SWMWACO3	220985.72	337669	ARC OF WASHINGTON COUNTY	820-840 FLORIDA AVE	ARC OF WASHINGTON COUNTY	IT	REC L 1199 F 1048	Satisfactory	6/10/2014	ZDR	None	7/3/2017
SWMCM	221312.82	338428.57	COUNTY MARKET	835 W HILLCREST RD	RIVELLINO TONY	IT	ON FILE 9/27/90 5/21/91	Satisfactory	7/14/2014	ZDR	None	11/15/2017
SWMGRBRTH	217918.02	337502.06	GRACE BRETHERN CHURCH	837 SPRUCE ST	SMITH DAVID H	IT	REC 12/8/92	Satisfactory	7/31/2014	ZDR	None	11/14/2017
SWMCMOFF1	217430.54	338914.98	C M OFFRAY PARKING LOT ADDN	857 WILLOW CIR	MONGAN SUE	IB	REC L 1254 F 0223	Satisfactory	8/2/2014	ZDR	None	9/29/2017
SWMELECTROMET	217660.16	338847.01	ELECTROMET CORP.	871 COMMONWEALTH AVE	NOT LISTED	IT	NONE	Deficiency	7/2/2014	ZDR	Send Letter	12/11/2017
SWMNEEDY	217730.05	337542.63	NEEDYS FURNITURE	901 S POTOMAC ST	NEEDY DAVID	UGS	ON FILE 9/10/92	Satisfactory	8/1/2014	ZDR	None	11/7/2017
SWMPNGHTS2A	220146.64	340187.65	PANGBORN HEIGHTS	SECURITY RD	STAMPER ANDY	DP	ON FILE 6/8/90	Satisfactory	6/10/2014	ZDR	None	7/7/2017
SWMHGBSPK2	218309.51	336455.14	HAGERSTOWN BUS PK	900-925 SWEENEY DR	MYERS LEROY	DP	REC L 1254 F 0236	Satisfactory	7/24/2014	ZDR	None	11/9/2017
SWMWIHGTS1	221510.73	338112.58	WEST IRVIN HEIGHTS	840-988 W IRVIN AVE	RIDER DAVE	IB	ON FILE 11/16/92	Deficiency	4/30/2014	ZDR	Send Letter	6/21/2017
SWMWIHGTS2	221368.913	221368.91	WEST INRVIN HEIGHTS	840-988 W IRVIN AVE	RIDER DAVE	IT	ON FILE 11/16/92	Deficiency	4/30/2014	ZDR	Send Letter	9/1/2017
SWMLOWES1	218167.04	336737.19	LOWES REGIONAL DISTRIBUTION CENTER	914 S BURHANS BLVD	BOWMAN DEVELOPMENT - AGENT IRV GISH	IT	NONE	Satisfactory	8/2/2014	ZDR	None	11/7/2017
SWMRAV	218637.35	336693.9	R E MITCHELL CO	915 S BURHANS BLVD	NOT LISTED	ED	NONE	Satisfactory	8/5/2014	ZDR	None	12/5/2017
SWMHGBSPK3	218310.96	336413.08	HAGERSTOWN BUS PK	919 SWEENEY DR	APRION	DP	NONE	Satisfactory	6/14/2014	ZDR	None	12/5/2017
SWMHINDPK1	217921.52	339174.67	HAGERSTOWN IND PK	920 ELDRIDGE DR	NOT LISTED	IT	NONE	Satisfactory	8/2/2014	ZDR	None	11/17/2017
SWMSCHSQ1	220181.62	336586.2	SCHOOL HOUSE SQ	920 W WASHINGTON ST	SAGI STEVE	IT	6/26/87	Satisfactory	7/14/2014	ZDR	None	11/8/2017
SWMSCHSQ2	220181.62	336586.2	SCHOOL HOUSE SQ	W WASHINGTON ST	SAGI STEVE	IT	6/26/87	Satisfactory	7/14/2014	ZDR	None	11/6/2017
SWMLARK	217887.07	339177.84	LARKIN WHOLESALE	929 ELDRIDGE DR	HOUSE JR DAVID	SM	ON FILE 3/24/92	Satisfactory	8/2/2014	ZDR	None	9/29/2017
SWMSUMMAN	220103.9	340113.51	SUMMERLAND MANOR	929 SECURITY RD	RIDER PERINI	DP	REC L 1595 F 0138	Deficiency	7/31/2014	ZDR	Send Letter	7/10/2017
SWMHINDPK2	217913.61	339192.64	HAGERSTOWN IND PK	930 ELDRIDGE DR	BAIR EMMERSON	IT	ON FILE 5/3/89	Satisfactory	8/1/2014	ZDR	None	11/17/2017
SWMSTCLAIR	221231.21	338498.31	SAINT CLAIRE APTS	933-958 SAINT CLAIRE ST	LYLES DAVID	DP	REC L 1963 F 0235	Deficiency	7/29/2014	ZDR	None	10/13/2017
SWMCHEVYCHASE4	218556.35	339780.91	CAVEY CHASE BANK	950 DUAL HIGHWAYS	CHEVY CHASE BANK	BIO	ON FILE 9/06/06	Satisfactory	6/9/2014	ZDR	None.	11/8/2017
SWMWAGAR	220099.4	340121.2	WASHINGTON GARDENS	950 SECURITY RD	NOT LISTED	DW	NONE	Satisfactory	7/14/2014	ZDR	Send Letter	7/7/2017
SWMHAGBB1	217344.25	338733.13	HAGERSTOWN BOOKBINDING & PUB	952 FREDERICK ST	SNYDER JOHN	DP	REC L 1963 F 0188 AGM	Deficiency	8/2/2014	ZDR	Send Letter	9/29/2017
SWMHAGBB2	217344.25	338733.13	HAGERSTOWN BOOKBINDING & PUB	952 FREDERICK ST	SNYDER JOHN	DP	REC L 1963 F 0188 AGM	Deficiency	8/2/2014	ZDR	Send Letter.	9/29/2017
SWMACTIONPRO	218429.33	336330.76	ACTION PRODUCTS	954 SWEENEY DR	McELROY BENEDICT	OGS	RE L 1346 F 0574	Satisfactory	7/31/2014	ZDR	None	10/18/2017
SWMLOWESDIST	218627.13	336722.15	LOWES DISTRIBUTION CTR	990 WESEL BLVD	LOWES HOME CENTERS, INC.	DP	ON FILE 9/19/03 REC L 1	Satisfactory	8/1/2014	ZDR	None	7/7/2017
SWMANTCAB1	217671.15	339244	ANTIETAM CABLE TV	1000 WILLOW CIR	NOT LISTED	DP	REC L 1200 F 0007	Satisfactory	7/1/2814	ZDR	None	9/29/2017
SWMNOLANDVILAGI	218298.85	336026.96	NOLAN VILLAGE	1000 NOLAN DR	CITY OF HAGERSTOWN DPW	IT	NONE	Satisfactory	7/14/2014	ZDR	None	12/11/2017
SWMHILLSIDES	220664.27	340682.98	HILLSIDE MANOR LLC	1004 BRILL WAY	HILLSIDE MANOR LLC	DP	NONE	Deficiency	6/13/2014	ZDR	Send letter	10/24/2017
SWMUPGL1	217496.12	337498.69	CLASSIC UPHOLSTERY & GLASS	1008 S POTOMAC ST	SHIPLEY JEFF	IT	ON FILE 10/28/07 REC L	Satisfactory	8/1/2014	ZDR	Send Letter	12/8/2017
SWMUPGL2	217432.5	337522.36	CLASSIC UPHOLSTERY & GLASS	1008 S. POTOMAC ST	SHIPLEY JEFF	IB	ON FILE 10/28/07	Deficiency	8/1/2014	ZDR	Send Letter	12/8/2017
SWMBRMAN2	221413.7	337747.07	BRIGHTON MANOR	923-1096 KASINOF AVE	CREATIVE INVEST	DP	REC L 1346 F 0653	Satisfactory	7/3/2014	ZDR	None	6/28/2017
SWMHGBSPK1	218331.29	336234.66	ALICES COUNTRY COTTAGE LOT 18	1010 McCAULEY CT	BLACKMAN OLAF	IT	REC L 1346 F 0605	Satisfactory	7/31/2014	ZDR	None	11/16/2017
SWMHLCHR	222295.03	338205.45	HAVEN LUTHERAN CHURCH	1035 HAVEN RD	EVAN HAVEN	DP	NONE	Satisfactory	4/30/2014	ZDR	None	6/28/2017
SWMYMCA2	221503.33	340730.75	YMCA	1100 EASTERN BLVD	FLICEK MIKE	DP	ANNEXED	Deficiency	4/30/2014	ZDR	Send letter regard	6/30/2017
SWMYMCA1	221323.04	340702.14	YMCA	1100 EASTERN BLVD N	FLICEK MIKE	DP	ANNEXED	Deficiency	4/30/2014	ZDR	Letter Sent	6/30/2017
SWMYMCA1A	221546.45	340510.29	YMCA	1100 EASTERN BLVD N	MICHAEL FLICEK	MP	ON FILE 06/17/2010 REC	Deficiency	4/30/2014	ZDR	None for Micro-pr	6/30/2017
SWMYMCA2A	221501.31	340728.22	YMCA	1100 EASTERN BLVD N	MICHAEL FLICEK	MP	ON FILE 06/17/2010 REC	Satisfactory	4/30/2014	ZDR	Send letter.	6/30/2017
SWMGOODHUMOR	216726.24	339053.17	GOOD HUMOR BREYERS ICE CREAM	1100 FREDERICK ST	GOOD HUMOR BREYERS ICE CREAM	BIO	ON FILE 8/09/06	Satisfactory	7/17/2014	ZDR	None.	7/14/2017
SWMGOODHUMOR2	216726.24	339053.17	GOOD HUMOR BREYERS ICE CREAM	1100 FREDERICK ST	GOOD HUMOR BREYERS ICE CREAM	BIO	ON FILE 8/09/06 REC L 3	Satisfactory		ZDR	None	7/14/2017
SWMMAACO	218610.85	340064.32	MAACO	1101 CONRAD CT	KANDRICK RICHARD	DP	REC L 1963 F 0174 AGM	Deficiency	7/3/2014	ZDR	None.	12/11/2017
SWMHILLSIDEN	220741.67	340682.98	HILLSIDE MANOR LLC	1102 STAR DR	HILLSIDE MANOR LLC	DP	NONE	Satisfactory	6/13/2014	ZDR	None	10/24/2017
SWMNHHS	220450.83	339470.69	NORTH HAGERSTOWN HS	1106 PENNSYLVANIA AVE	CITY OF HAGERSTOWN DPW	ED	NONE	Deficiency	4/30/2014	ZDR	Send Letter	10/13/2017
SWMNG2	221490.83	338242.02	NORTHGATE 2	1108 FAIRCHILD AVE & W IRVIN AVE	RIDER DAVE	IB	ON FILE 11/16/92	Satisfactory	7/14/2014	ZDR	None	6/21/2017
SWMREDCROSS	218525.33	340162.6	RED CROSS	1131 CONRAD CT	RED CROSS AMERICAN NATIONAL	DP	NONE	Deficiency	7/3/2014	ZDR	Send Letter.	11/3/2017
SWMOPCRT	218754.42	340371.09	DR. WEISS, BECKER, SHUSTER & BUDI	1141 OPAL COURT	DR. WEISS, BECKER, SHUSTER & BUDI	WQ	ON FILE 9/21/06	Satisfactory	7/3/2014	ZDR	None	11/3/2017
SWMRLV1	216821.4	338433.63	RAVENWOOD LUTHERAN VILLAGE	1158-1183 LUTHER DR	FRALICK DAVE	DP	REC L 1220 F 0364	Satisfactory	6/9/2014	ZDR	None.	7/3/2017
SWMCMW	218489.44	340295.36	CMW, LLC	CONRAD COURT	CMW, LLC	DP	ON FILE 2/10/05	Satisfactory	7/3/2014	ZDR	None	11/3/2017
SWMBBC1	218879.5	340508.5	BBC DEV & MGT	1175 PROFESSIONAL CT	JOHNSON BOB	DP	REC L 1418 F 0876	Satisfactory	7/4/2014	ZDR	None. Check abo	10/24/2017
SWMMENTALHLTH	218989.46	340665.52	WASH CO MENTAL HEALTH	1180 PROFESSIONAL CT	WASH CO MENTAL HEALTH	DP	NONE	Deficiency	7/3/2014	ZDR	Send Letter.	10/16/2017
SWMNG1	221933.8	337690.27	NORTHGATE 1	BEECHWOOD DR & FAIRCHILD AVE	RIDER DAVE	IB	ON FILE 11/16/92	Satisfactory	4/30/2014	ZDR	None	6/28/2017
SWMROCKY	216974.23	336671.02	ROCKYS TOP WOOD PRESERVERS	1201 MARYLAND AVE	GARST GARY	IT+DP	REC L 1346 F 0612	Satisfactory	8/5/2014	ZDR	None	11/9/2017
SWMLOWES2B	217172.96	336733.52	LOWES - MD AVE	1205 MARYLAND AVE	GROH VINCENT	DP	NONE	Deficiency	8/13/2014	ZDR	Send Letter.	11/8/2017
SWMSUP8	218173.72	339873.8	SUPER 8 MOTEL	1220 DUAL HWY	ABERDEEN	IT	11/11/96	Satisfactory	7/30/2014	ZDR	None	8/17/2017
SWMLOWES2A	217011.17	336589.15	LOWES - MD AVE	1227 MARYLAND AVE	GROH VINCENT	DP	NONE	Satisfactory	8/13/2014	ZDR	None	11/8/2017
SWM1200POTO	221241.03	339663.03	POTOMAC AVE 1200	1236 E MAGNOLIA CT	CITY OF HAGERSTOWN DPW	IT	PER 12/27/91 MEMO BY	Satisfactory	7/31/2014	ZDR	None	10/18/2017
SWMBDCU1	218131.38	339894.08	BULLDOG FEDERAL CREDIT UNION	1240 DUAL HWY	VAN WYK BRUCE & DAVE BARRETT	IT	ON FILE 10/31/02	Satisfactory	8/1/2014	ZDR	None	11/15/2017
SWMNORMOR	216693.42	336521.04	NORMAN MORGAN	1246 MARYLAND AVE	MORGAN NORMAN	IT	ON FILE 2/27/92	Satisfactory	7/15/2014	ZDR	None	12/5/2017
SWMBRICKER	218904.55	335223.28	BRICKER ENTERPRISES	1280 WESEL BLVD	BRICKER ENTERPRISES	ITPE	ON FILE 3/31/04	Deficiency	4/30/2014	ZDR	Send Letter.	7/21/2017

SWMWIHTMS	221373.05	337274.71	WESTERN HEIGHTS MS	1300 MARSHALL ST	W C B O E	DP	L 1154 F 0975	Satisfactory	6/4/2014 ZDR	None	7/3/2017
SWMDBMDWS	216818	337321.54	DOUB MEADOWS	1300 S POTOMAC ST	NOT LISTED	DP	NONE	Satisfactory	5/12/2014 ZDR	None	7/3/2017
SWMRITAS	221928.98	338299.54	RITAS ICE CREAM	1313 PENNSYLVANIA AVE	MYERS DENNIS	DP	REC L 1963 F 0220 AGM	Satisfactory	4/30/2014 ZDR	Follow-up inspect	6/28/2017
SWMSALES	221250.36	336865.79	SALEM AVENUE ELEMENTARY SCHOOL	1323 SALEM AVE.	WASHCO BOARD OF ED.	ED	ON FILE 3/4/05	Satisfactory	7/3/2014 ZDR	None	7/3/2017
SWMDFFH1	221516.19	340416.09	DOUGLAS A FIERY FUNERAL HOME	1331 EASTERN BLVD N	FIERY ROGER	UGS	REC 3/13/91	Satisfactory	7/31/2014 ZDR	None	8/17/2017
SWMDFFH2	221516.19	340416.09	DOUGLAS A FIERY FUNERAL HOME	1331 EASTERN BLVD N	FIERY ROGER	UGS	REC 3/13/91	Satisfactory	8/2/2014 ZDR	None	8/17/2017
SWMNOLND	218766.17	335197.66	NOLAND CO	1350 WESEL BLVD	NOLAND JR LLOYD	IT	REC L 1220 F 0382	Satisfactory	7/14/2014 ZDR	None	12/5/2017
SWMHYDEPRK	222530.47	337361.21	HYDE PARK APTS	1435 KENSINGTON AVE	SAY JOHN	DP	NONE	Deficiency	7/3/2014 ZDR	Send Letter.	6/28/2017
SWMNWIN1	218665.18	335056.89	NATIONWIDE INSURANCE	1441 WESEL BLVD	DOUGLES WILLIAM	ED	ON FILE 4/9/92	Satisfactory	7/24/2014 ZDR	None. Facility eli	12/1/2017
SWMLOWES	218766.17	335197.66	RDC PROJECTS, INC.	1448 WESEL BLVD	BOWMAN DEVELOPMENT	DP	ON FILE 3/24/08	Deficiency	8/2/2014 ZDR	Send Letter.	12/8/2017
SWMAPBEES1	218609.32	334964.56	APPLEBEES RESTAURANT	1481 WESEL BLVD	BOWMAN TODD	DP	REC L 1254 F 0214	Satisfactory	7/3/2014 ZDR	None	12/1/2017
SWMC&SPLAZA1	221712.14	336525.72	C & S PLAZA	1481 SALEM AVE	REID GARY A & CINDY D	DP	NONE	Satisfactory	6/9/2014 ZDR	None.	7/3/2017
SWMC&SPLAZA2	221702.7	336571.48	C & S PLAZA	1481 SALEM AVE	REID GARY A & CINDY D	DP	NONE	Satisfactory	6/9/2014 ZDR	None	7/3/2017
SWMCV2	221881.758	339784.54	CVS PHARMACY	1500 POTOMAC AVE	F. B. HAGERSTOWN, LLC.	UGS	ON FILE 5/18/09 REC L 4	Satisfactory	8/1/2014 ZDR	None.	11/15/2017
SWMLOWESOLD	218451.39	335042.28	LOWES - OLD	1501 WESEL BLVD.	LOWES HOME CENTERS, INC.	DP		Deficiency	4/24/2014 ZDR	Send Letter	12/1/2017
SWMWDLNDN	222572.09	337155.6	WOODLANDS NORTH	1500-1547 KENSINGTON DR	ENT CLAGETT	IT	NONE	Satisfactory	7/3/2014 ZDR	None	12/5/2017
SWMSTANNS	221830.54	339531.98	SAINT ANNS CHURCH	1525 OAK HILL AVE	REV WILLIAM KEEFER	IT	ON FILE 8/16/89	Satisfactory	7/3/2014 ZDR	None	6/28/2017
SWMHGRTRUST	218426.26	334752.07	HAGERSTOWN TRUST	1581 WESEL BLVD	STONERIDGE DEVEL CORP	DP	NONE	Satisfactory	7/24/2014 ZDR	None	12/5/2017
SWMTIRESPLUS	216851.04	340548.24	TIRES PLUS	1622 DUAL HWY	BRIDGESTONE RETAIL OPERATIONS, LLC.	DP	ON FILE 09/23/10 REC L	Satisfactory	8/2/2014 ZDR	None	7/10/2017
SWMDENNY1	216921.33	340445.55	DENNYS RESTAURANT	1630 DUAL HWY	CNL FUND % ROBERT BORNE	UGS	REC L 1220 F 0390	Satisfactory	7/30/2014 ZDR	None	7/10/2017
SWMHTB1	216921.33	340445.55	HAGERSTOWN TRUST BANK	1630 DUAL HWY	BOURNE BOB	UGS	REC L 1220 F 0397	Satisfactory	8/1/2014 ZDR	None	7/10/2017
SWMWALGREENS	216649.03	340451.28	WALGREENS - DUAL HIGHWAY	1631 DUAL HWY	BSM DUAL HIGHWAY LLC	UGS	ON FILE 3/11/14 L 4724 F	Satisfactory	8/1/2014 ZDR	None	11/6/2017
SWMJIFFYLUBE	218354.68	334535.93	JIFFY LUBE	1648 WESEL BLVD	HAGERSTOWN PAD, LLC.	BIO	REC L 4696 F 0135	Satisfactory	7/14/2014 ZDR	None	12/5/2017
SWMHOMFED	216656.11	340571.49	HOME FEDERAL BANK ADDN	1700 DUAL HWY	NOT LISTED	IT	NONE	Satisfactory	8/5/2014 ZDR	None	11/16/2017
SWMVALPRK	218290.99	334524.04	VALLEY PARK	1700 WESEL BLVD	DOUGLAS WILLIAM	DP	ON FILE 4/9/92	Satisfactory	7/24/2014 ZDR	Check site plans	7/14/2017
SWMPNC1	216609.99	340597.76	PNC BANK	1700 DUAL HIGHWAY	PNC BANK, N.A.	ESDMB	ON FILE 03/11/14 REC L	Deficiency	8/1/2014 ZDR	Send Letter.	7/10/2017
SWMPNC2	216651.99	340579.3	PNC BANK	1700 DUAL HIGHWAY	PNC BANK, N.A.	ESDMB	ON FILE 03/11/14 REC L	Satisfactory	8/1/2014 ZDR	Letter Sent	7/10/2017
SWMPNC3	216651.99	340579.3	PNC BANK	1700 DUAL HIGHWAY	PNC BANK, N.A.	ESDMB	ON FILE 03/11/14 REC L	Deficiency	8/1/2014 ZDR	None	7/10/2017
SWMPNC4	216651.99	340579.3	PNC BANK	1700 DUAL HIGHWAY	PNC BANK, N.A.	ESDMB	ON FILE 03/11/14 REC L	Deficiency	8/1/2014 ZDR	None	7/10/2017
SWMPNC5	216651.99	340579.3	PNC BANK	1700 DUAL HIGHWAY	PNC BANK, N.A.	ESDMB	ON FILE 03/11/14 REC L	Satisfactory	8/1/2014 ZDR	Letter Sent	7/10/2017
SWMHAMINN	216629.38	340583.31	HAMPTON INN	1716 DUAL HWY	FALLING SPRING CORP	UGS	REC L 1254 F 0206	Satisfactory	7/24/2014 ZDR	None	7/10/2017
SWMHEART	216969.08	340117.94	HAGERSTOWN HEART FACILITY	1733 HOWELL RD	HAGERSTOWN HEART PROPERTIES, LLC.	DP	ON FILE 7/16/03	Deficiency	7/24/2014 ZDR	Send Letter	7/10/2017
SWMTRIELEC	216424.82	340616.97	TRISTATE ELECTRIC	1741 DUAL HWY	NOT LISTED	IT	NONE	Satisfactory	7/24/2014 ZDR	None	12/5/2017
SWMEDGHIL	216573.67	340607.79	EDGEWOOD HILLS CONDOS	1750 DUAL HWY	NOT LISTED	DP	NONE	Satisfactory	7/31/2014 ZDR	None	7/10/2017
SWMNWWK	216878.66	340215.95	NWWK INC	1825 HOPEWELL RD	DR WOOSTER	DP	ON FILE 10/6/89	Satisfactory	7/24/2014 ZDR	Send Letter	7/17/2017
SWMIBM1	216392.07	340688.86	IBM	1850 DUAL HWY	HARRISON R L	DP	NONE	Satisfactory	7/24/2014 ZDR	None	7/10/2017
SWMWADE	216804.64	340270.16	WADE DENTAL OFFICE	1855 HOWELL RD	MARGRET L. WADE	UGS	ON FILE 4/11/03	Satisfactory	7/24/2014 ZDR	None	7/17/2017
SWMLONDN	215908.4	341518.27	LONDONTOWNE	1840-1938 ABBY LN	SHEEDY DAN	DP	NONE	Satisfactory	8/5/2014 ZDR	None	7/10/2017
SWMGREPRK	216834.34	341977.73	GREENWICH PARK	1900 MERIDIAN DR	CHURCHEY WES	DP	REC L 1963 F 0180 AGM	Satisfactory	7/18/2014 ZDR	None	7/10/2017
SWMHAMNIS	215359.64	341107.06	HAMILTON NISSAN	1929 DUAL HWY	HAMILTON RICHARD	DP	REC L 1963 F 0194 AGM	Deficiency	7/24/2014 ZDR	Send Letter	7/10/2017
SWMHAGCMCTR	215318.41	341126.5	HAGERSTOWN COMMERCE CTR	1935 DUAL HWY	COHEN RANDY	DP	L 1595 F 0189	Satisfactory	6/9/2014 ZDR	None	10/10/2017
SWMYOUNMTR	215052.99	340993.67	YOUNGER MOTOR CARS	1945 DUAL HIGHWAY	BRANDON YOUNGER - YOUNGER MOTOR C	WQ+SF	ON FILE 1/2/07	Satisfactory	4/30/2014 ZDR	None	6/26/2017
SWMLYLESCENTER	222512.84	340084.97	LYLES VENTURES BUILDING	12916 CONAMAR DR	LEITERSBURG PIKE, LLC	IT	ON FILE 5/22/06	Deficiency	6/13/2014 ZDR	Send Letter	6/20/2017
SWMHAGPLZ2	221786.36	336072.01	HAGERSTOWN PLAZA	18053 GARLAND GROH BLVD	UNIWEST GROUP, LLC.	ED	ON FILE 9/21/06	Deficiency	6/9/2014 ZDR	Send Letter.	7/3/2017



# CITY OF HAGERSTOWN, MARYLAND

Department of Parks and Engineering

10/09/17



Frederick, MD 21702

RE: Storm water Management Structure  
Preventative Maintenance Inspection  
Notice of Deficiencies

To Whom it May Concern:

During the development of property in the City of Hagerstown, owners agree to maintain all Storm water Management Structures constructed during the development.

Maryland State Law and the Code of the City of Hagerstown, Section 213.24 requires that the office of the City Engineer inspect all Storm water Management Structures in the City of Hagerstown. This inspection is completed on a tri-annual basis, and verifies the structure is operating as designed, does not pose any danger to the public health or safety, and is being maintained as agreed by the owner.

During our inspection of Storm Water Management Pond located at [REDACTED] our staff determined that the following conditions should be corrected by your forces:

- Remove trash from Storm water management structure
- Remove trees within 25' of weir / concrete wall

Kindly address these required maintenance items within by November 24, 2017. Failure to do so may result in penalties outlined in Section 213.29 of the City Code. We would be happy to meet with you on site to discuss these problems at your earliest convenience.

Sincerely,

CITY OF HAGERSTOWN

Zach Rawe  
Engineer Technician III

Attachments: As applicable  
c: Rodney Tissue  
Inspection file

## **Pollution Prevention/Good Housekeeping**


In order to encourage the general public to participate in the stormwater pollution prevention program, it is important for the City to set a good example. As part of this process, the City is performing an inventory of all City-owned properties to identify problems and potential solutions related to stormwater runoff.

The first step in this process was for the City to prepare a map that located all of the City-owned properties within the corporate boundary. Using the City's GIS system and the Maryland Department of Assessments and Taxation database, the Engineering and Inspections Department prepared a "City Owned Property" map. This map highlighted the various parcels inside the corporate boundary that list the "City of Hagerstown" as the owner.

The City is continues to inventory and monitor properties that are used daily in providing government services to its residents. As mentioned in the previous section, the City was fortunate to be awarded funding from the Chesapeake and Atlantic Coastal Bays Trust Fund to construct two stormwater retrofit facilities, both of which help to improve water quality at two City-owned facilities where little or no stormwater management existed:

### **Hagerstown Light Department/Central Maintenance Garage:**

This facility houses the City's Electrical Service Department, as well as the maintenance facility for the City's fleet of vehicles. The site, as shown below, consists of a large warehouse building, paved parking lots, and a large gravel storage yard.



Hagerstown Light Department/Central Maintenance Garage facility

Using a grant from the Chesapeake and Atlantic Coastal Bays Trust Fund, the City constructed a bioswale with timber weirs immediately to the south of the facility. The bioswale now provides treatment for runoff from the Light Department facility, as well as a private paved parking lot to the west.



Drainage channel prior to project



Bioswale and timber weir installation during construction



Completed bioswale

According to the design calculations, this facility will reduce annual Nitrogen loads from the drainage area by 36.9 pounds; 9.3 pounds of Phosphorus and 2.7 tons of sediment will also be removed.

The Light Department is responsible for electric power distribution throughout the City, and they maintain a fleet of vehicles (bucket trucks, dump trucks, support vehicles, etc.) for this purpose. The Light Department also uses the large paved area behind the building as a storage yard for utility poles, light fixtures, and other electrical equipment. Any work on transformers or other electrical components is performed inside the building, and any wastes from these activities are contained until they can be properly disposed. The Central Maintenance Garage facility is the shop where all City vehicles are serviced. All of the service work is performed inside the work bays of the shop. All vehicle fluids (oil, lubricants, antifreeze, etc.) are captured and contained in the bays, and are stored for recycling or proper disposal. Staff working at this facility have been trained in spill containment, and absorbent materials are available to assist with the clean-up of any spills. Staff receives refresher training periodically.

## Wastewater Treatment Plant

The City's wastewater treatment plant is a sprawling facility on the southeast side of the City (see photo below). The site is adjacent to Antietam Creek, and effluent from the treatment process is discharged into the stream.



The plant itself has an NPDES permit, and maintains its own SWPPP program. However, using grant funds from the Chesapeake and Atlantic Coastal Bays Trust Fund, the City was able to construct a stormwater management retrofit facility at the site that provides treatment for a portion of the City facility and adjoining industrial properties. The facility, a large bioretention filter, provides treatment for the “first flush” of runoff from the watershed. The completed facility provides annual pollutant/nutrient reductions of 100 lbs. N, 21 lbs. P, and 5.8 tons of sediment. The photos below document the facility's construction.



Pre-construction photo of bioretention site



Bio-retention facility under construction



Completed facility during a storm event

The Wastewater Treatment Plant site is permitted and monitored by the Maryland Department of the Environment. Staff at the plant are trained to safely transport and use chemicals and materials required by the wastewater treatment process. These materials are contained in storage facilities designed to protect them from unauthorized access, and they are protected from the elements so that they have limited impact on stormwater runoff. Because this is a critical operation that is monitored through the City's wastewater discharge permit, staff are continually reviewing and updating policies and procedures to ensure compliance.

## **Public Works Department**

The City's Public Works facility presents a challenge to stormwater pollution control given its relatively tight layout and highly impervious surface coverage. Storm runoff from the site either sheet flows off into the rights-of-way of Memorial Blvd. and Garlinger Avenue, or is collected in an existing storm drain that discharges into Marsh Run at the railroad overpass. The site includes salt and gravel stockpile areas, an enclosed shop area, and a fueling station.




Department of Public Works facility – 51 W. Memorial Blvd.

Public Works staff has been trained to contain fuel and oil spills, and absorbent materials are available on-site to pick-up spilled material. The salt storage area is covered to protect it from rain and the elements; however, staff is investigating ways to capture and contain runoff from this area prior to its discharge into Marsh Run. In early 2009, the City replaced the fuel station facility at this location; this work included the installation of new underground fuel storage tanks with containment facilities, along with new fuel pumps and safety features. This new fuel facility has helped to minimize the potential for fuel/contaminant discharges to adjacent storm drainage facilities. The City also purchased training materials from Excal Visual, Inc.; these materials included a video presentation intended to instill good housekeeping techniques (e.g. spill containment, construction site cleanup, etc.) and considerations in the minds of the Public Works staff. Periodic staff meetings are held to review these procedures, along with property safety practices. The City is also considering alternative methods for salt storage, which would decrease the potential for salt-laden runoff entering the storm drainage system.

The City also has an ongoing street sweeping program; a map of the downtown street sweeping route map is attached. The City recently expanded the downtown sweeping area, providing more sediment collection for the densely-developed core area. Street sweeping helps to collect pollutants and contaminants on our streets before they are washed into the storm drainage system. The City's 110 miles of streets are swept weekly on a rotating basis, with an emphasis on the downtown core area; the following photo shows an example of an advisory sign posted along one of our streets, and one of the City's street sweepers in action. Public Works reports that, together, the two sweeping units average approximately 15,000 lane miles swept each year.





—— 9:00 - 11:00 AM    
 —— 6:00 - 8:00 AM

**MONDAYS:**     NORTH SIDE OF STREET SWEEP  
**TUESDAYS:**    SOUTH SIDE OF STREET SWEEP  
**WEDNESDAYS:** WEST SIDE OF STREET SWEEP  
**THURSDAYS:**   EAST SIDE OF STREET SWEEP

# CITY CENTER STREET SWEEPING SCHEDULE

LAST REVISED: SEP 11 '17